

CHAPTER 4

RESULT AND COMPARISON



The implementation and the results of the existing model and the proposed model will be presented in this chapter. The existing and the proposed model will be implemented for the projects of MD, which are Ratchaburi Thermal Power Plant Project Construction (RTPP) and Krabi Thermal Power Plant Project Construction (KTPP) under the assumption mentioned in Chapter 2. The projects are independent, which means that there is no relation between job activities of the projects while the MD's resource which is pooled resource is used for both projects.

4.1 The Results of Existing Model

The existing model consists of Demand, Planning, and Allocation. The results of the existing model are shown below. Relevant information which will be used for this model came from daily report. The daily report records all necessary data of work such as name of job activity and its duration, contractor, name and number of inspector, starting and finishing time, etc. The daily report form is shown in Appendix C.

4.1.1 Result of the STEP 1

The job activity, milestone and duration, and budget of the project schedules are reviewed based on the starting and finishing mechanical work schedule. The demanded resource, which usually consists of Chief of mechanical project department (CMPD), Head of project section (HMPS), engineer (ENG.), foreman (FORE.), administrators (ADM.), some inspectors (INS.) were identified in unit and name. CMPD, HMPS, ENG. and FORE, ADM. and some inspectors of the projects were assigned and planned to work along the project schedules. However, there were some remaining inspectors who would be allocated to either project. Therefore, the cost of human resource was estimated due to demand. The cost could be grouped into two types: Standard Rate, and Overtime Rate. The standard rate was an average rate consisting of salary, electricity allowance,

providence allowance, position allowance, fringe benefit and travel cost. The overtime rate was an expenditure occurring when the human resource worked on extra time, e.g., in the morning, at noon, in the evening and during holidays. The multiplying of unit and cost was the estimation of the budget. All cost data come from the Account and Treasury Department and then the cost is calculated to be an averaged cost. The actual numbers of resource allocation demand and allocation are collected from the daily report of the old projects.

4.1.2 Result of the STEP 2

The human resource allocation was planned regarding to the demand by CMPD. The demand caused some resources including the locked resources for the projects, some inspectors, to be assigned to the projects while some remaining resources could still be allocated to either project. However, some inspectors had already been planed to allocate to the project 1 as the first priority because it started before the project 2. Then remaining resources were allocated to the project 2. Later on, when there was additional resource demand for the project 2, some resources that had returned from project 1 to MD after its demand has decreased can be allocated to project 2.

4.1.3 Result of the STEP 3

The resource was allocated following and depending on the projects' demand which was the demand from CMPD. The allocation between MD and the projects occurred when CMPD required or decreased the resource. There were two types of allocation: from MD to the Projects and from the Projects to MD. According to the daily report and verbal interviewing of CMPD and CMPD of old projects of MD, the allocation in this step is a pattern of a practical allocation of MD.

- **MD to Projects**

Typically, the resource was allocated from MD to both projects at the beginning of the projects. First, the locked resource, some inspectors were allocated to project 1 and the allocation of the remaining resource who were inspectors increased when the demand

increased. The resource included the locked resource for the project 1 and the remaining resource for both projects. This method of allocation resulted in lack of resource, the inspectors, for Project 2 when the two projects were overlapping and when the resource demand of project 1 decreased but its CMPD did not allocate the resource back to the MD following the plan. The problems that occur were over supply of resource for the project 1 and shortage of resource for the project 2. The budget of the project 1 was higher than that of the plan. CMPD of the project 2 solved the problems by increasing overtime. During the project construction, relevant information of work was recorded in the daily report. If the resource shortage occurred, over time was established in order to finish work. This caused the extra cost. The shortage of resource was derived from the daily report.

- **Projects to MD**

The resource was allocated from both projects to MD when demands decreased and/or the projects had been finished. In general, the resource of the projects should be allocated to MD when the projects' demand decreased. In this case, although the demand of the project 2 increased, during the overlapping of both projects, the resource was still assigned in project 1 because CMPD of the project 1 did not return the resource to MD. The main reason of the resource assignment was that CMPD considered the finishing date of the last activity as the first priority. Therefore, CMPD's idea is that the more resources, the higher quality of work. That resulted in over supplying of resource in the project 1 after the demand had already decreased and, at the same time, there was already shortage of resource in the project 2 when the demand was higher than the resource available at the project. In addition, the resource was lately allocated to MD because the CMPD still assigned them work in the projects.

According to the results of existing model, chief of mechanical project department, engineer, foreman and administrator were worked from starting to finishing projects. Only inspectors were varied in unit working in the projects. Therefore, the allocation data in terms of unit and cost of the inspector will be used to study.

The actually work and overtime of inspector of each section during the projects' construction is also collected from the daily report. Working time of the resource are

seven days per week (Monday to Friday) and seven hours per day (8 a.m. to 4 p.m.). The unit of the resource is converted into workload value in hour before putting into Microsoft Project Program.

Actual cost of the resource is calculated by multiplying the workload with the averaged cost. Then the actual cost will be compared to the one of the proposed model. The averaged cost of the inspectors: Steam Generator Inspector (SGI), Mechanical Machine Inspector (MMI), Piping Inspector (PI) and Mechanical Equipment Quality Inspector (MEQII) are presented in Table 2.

Table 4.1: Averaged cost of the resources

| Item | Position | | | |
|-------------------------------|-----------|-----------|-----------|-----------|
| | SGI | MMI | PI | MIQII |
| Salary (Baht/month) | 28,000.00 | 27,000.00 | 27,500.00 | 29,000.00 |
| Average Salary (Baht/hr) | 133.33 | 128.57 | 130.95 | 138.10 |
| Site Allowance (Baht/day) | 500.00 | 500.00 | 500.00 | 500.00 |
| Site Allowance (Baht/hr) | 71.43 | 71.43 | 71.43 | 71.43 |
| Providence Fund (Baht/day) | 300.00 | 300.00 | 300.00 | 300.00 |
| Providence Fund (Baht/hr) | 42.86 | 42.86 | 42.86 | 42.86 |
| Fringe Benefit (Baht/day) | 168.00 | 162.00 | 165.00 | 174.00 |
| Fringe Benefit (Baht/hr) | 24.00 | 23.14 | 23.57 | 24.86 |
| Standard Rate (Baht/hr) | 273.76 | 268.14 | 270.95 | 279.38 |
| Overtime Rate (Baht/hr) | 200.00 | 192.86 | 196.43 | 207.14 |

The result of over supplying of resource did not cause the project 1 to delay because the starting and finishing dates of its job activity was fixed and the activity could be finished on the project schedule by MD's contractor. However, the over supplying resulted in higher cost for project 1. On the other hand, the shortage of resource caused over time

cost occurs in project 2. The actual workload in hour and cost of the plan and allocation of the old projects are put into the Microsoft Project Program.

4.2 Results of Proposed Model

The implementation of the proposed model consists of five steps: Work Scheduling, Resource Assignment, Allocation Plan, Allocation and Monitoring. The results are as follow.

4.2.1 Result of the STEP 1: Work Scheduling

This step starts with Gantt chart which shows job activities in task. Then, the resource demand will be identified in group and number.

Gantt chart which shows the activities of both projects are shown in Appendix A. As the MD is responsible for the project1 and 2, scope of work for the Mechanical Project Department (MPD) is described in Appendix B.

MD has four sections: Steam Generator Section (SGS), Mechanical Machine Section (MMS), Piping Section (PS) and Mechanical Equipment Quality Inspection Section (MEQI). The organization chart of MD is shown in Figure 3.3. Gantt chart which shows the mechanical work schedules of MD is presented in Figure 3.4.




Figure 3.3: Organization chart of MD

Figure 3.4: Gantt chart of RTPP and KTPP





Figure 3.4: Gantt chart of RTPP and KTPP



At present, there is no framework document of the human resource management. Therefore, the framework should be created to identify the resource groups. However, the framework of MD can be clarified from information of the previous projects. The framework used in this study consists of four groups which conform to the working sections.

- **Steam Generator Project Section (SGPS)**

This section takes the responsibility of construction, supervision and installation of steam generator plant including structural steel, ducting, boiler and high pressure vessels which is pressure part such as tube and non pressure part such boiler components and insulation.

- **Mechanical Machine Project Section (MMPS)**

This section is responsible for mechanical equipment construction, supervision and installation of mechanical equipment for thermal power plant, e.g., steam turbine and generator, water treatment plant, cooling tower and (HVAC) system.

- **Piping Project Section (PPS)**

The scope of work of this section consists of construction, supervision and installation of piping system for thermal power plant including steam piping, water piping, oil piping and gas piping systems.

- **Mechanical Equipment Quality Inspection Project Section (MEQI)**

This section provides services in nondestructive testing of welding work in compliance with international code and standard in the field of thermal power plant construction work.

Resource demand

There are six groups of MD's personnel: Chief of Mechanical Project Department (CMPD), Head of Project Section (HPS), Engineer, Foreman, Inspector and

Administrator. The personnel of the resource demand MD is combined and look for the resource usage. Number of the resource is arranged following the combined resource usage of the projects. It means the resources are constrained. Moreover, the resource usage of the combined projects for the proposed model is the same group and number and its cost as of the existing model. Therefore, it can be said that the environment in term of the resource usage is not different between both models. Details of the personnel in unit and their costs are the same as that of the existing model.

- **Chief of Mechanical Project Department (CMPD)**

This person is a mechanical department leader who creates and also manages a mechanical project department tentative time schedule in order that it meets the target goals in terms of time and cost. The chief also has control of resource management, e.g., manpower, money, equipment and materials, and management process of MD. Therefore, the chief should have both managerial and technical knowledge and experiences relating to MD's scope of work.

- **Head of Project Section (HPS)**

This person is responsible for a section under CMPD. The head creates and manages a section's tentative time schedule conforming to MD's schedule. The head works under CMPD and manage the work of engineers, foremen and inspectors in the section. The head should have knowledge and experience on the project section work.

- **Administrator (ADM.)**

This person has a supporting role in the office including documentation, inventory, transportation and overhead costs, which are mainly staff costs of the personnel in MD such as salary, benefits, overtime cost, travel cost, etc.

- **Engineer (ENG.)**

This person supervises specific disciplines of section's work to ensure that the mechanical equipment is assembled and installed in accordance with the relevant drawing and specification obligations. The engineer is under HMPS and manages the work of foremen and inspectors so that he should have knowledge and experiences, especially technical, in the section's work.

The engineer reports to HPS and reviews data and drawings, calculations, layouts, and other requirements related to mechanical aspects as to be submitted by the contractors and as required by the project. In addition the engineer provides recommendations and preparation of contract variation and change orders, if any.

- **Foreman (FORE.)**

This person follows an engineer's plan and manages inspectors' work whose job is always working on site. Foreman should have knowledge and experiences in mechanical assembly, installation inspection and managing inspectors.

- **Inspector (INS.)**

This person works by following an engineer's plan under a foreman and has direct contacts to MD's contractors at site. Therefore, the inspector should have knowledge and experiences in mechanical equipment assembly and installation inspection.

4.2.2 Result of the STEP 2: Resource Assignment

The resource demand in position and unit of each project is determined. Then the resource availability is group and number. Finally, the resource availability will be assigned for the projects according to the demand.

4.2.3 Result of the STEP 3: Allocation Plan

In this step, the CMD and CMPDs are involved in planning so that the plan closely represents the demand. There are four types of allocations which are from MD to Project 1 and 2, Internal Allocation, Project 1 and Project 2, and Project 1 and 2 to MD.

1. MD to Project 1 and 2

At the beginning, the resource is planned to allocate to Project 1 and the allocation will be increased as the Project proceeds and its allocation increased according to the demand. The resource is also planned to allocate to Project 2 when there is demand at the beginning of Project 2. Therefore, CMPD, HMPS, ENG., FORE., ADM., who are fixed for both projects, some inspectors are planned to allocate to the projects when their demands occurred.

2. Project 1 and Project 2

During the overlapping of Project 1 and Project 2 and when demand of Project 1 decreases, the resource who is inspector will be allocated from Project 1 to Project 2. The decrease of demand for inspectors resulting in reduction of their number from Project 1 and allocation of some as needed to Project 2.

3. Internal Allocation

When the work activities changed the resource who is inspector will be allocated from one to the other activities within Project.

4. Project 1 and 2 to the MD

When the demand of both projects decrease after the job activity or the Projects have been finished, the resource will be allocated back to MD. The CMPD, HMPS, ENG., FORE., ADM., the inspectors, who finish their job activities and there are not inspector's

demand from Project 2, of Project 1 and the resource of Project 2 who finish their job activities will be allocated to the MD.

4.2.4 Result of the STEP 4: Allocation

The resource is allocated according to the allocation plan. Most of the resource is allocated to Project 1 and then to Project 2 when the demand of resource for Project 1 has decreased and the job activity is over. Chief of Mechanical Project Department (CMPD), Head of Mechanical Project Section (HMPS), engineer (ENG.), foreman (FORE.) and administrator (ADM.) are allocated to the projects specifically in name and number at the very early stage of planning whereas the name and number of inspectors do not have to be fixed until later on. The fixed resources are necessary to manage and work throughout the projects from the projects' starting to finishing dates. Inspectors of each section can then be allocated to the projects accordingly.

4.2.5 Result of the STEP 5: Monitoring

The allocation is monitored all the time against the change of demand in case the mechanical schedule changed. Changes occur when demand is changed and the allocation is adjusted following the allocation step. Number of the resource allocation is evaluated comparing to the demand.

4.3 The result of Existing and Proposed Model Implementation

The results of implementation for the existing and the proposed model has shown the resource demand and actual allocation includes an actual data of human resource demand and cost of the finished projects, which are from 4 August 1997 to 4 August 2000 and from 4 August 1999 to 24 September 2002 of RTPP and KTPP, respectively. The resource allocation and cost of both models are different. Actual resource allocation and cost of the existing model are illustrated in Table 4.2 and 4.3, respectively. The demand, the allocation and their costs of the proposed model implementation are the same as that of the existing model because a maximum peak which is the highest number of the resource usage at each time could be allocated to fulfill the demand by following the proposed

model. Therefore, the resource allocation and cost of the proposed model is the same as the demand in position and unit as presented in Table 4.4 and 4.5, respectively.

Table 4.2: The resource utilization of the existing model

| | Jul '97 | Aug '97 | Sep '97 | Oct '97 | Nov '97 | Dec '97 | Jan '98 | Feb '98 | Mar '98 | Apr '98 | May '98 | Jun '98 | Jul '98 |
|---|---------|----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| Steam Generator Inspector | | 3 | 3 | 3 | 5 | 9 | 11 | 11 | 11 | 11 | 14 | 15 | 15 |
| Structural Steel and Duct | | 3 | 3 | 3 | 5 | 5 | 5 | 5 | 5 | 5 | 6 | 6 | 6 |
| Pressure part | | | | | | 4 | 6 | 6 | 6 | 6 | 8 | 9 | 9 |
| Structural Steel and Duct | | | | | | | | | | | | | |
| Pressure part | | | | | | | | | | | | | |
| Mechanical Machine Inspector | | 3 | 8 | 8 | 8 | 8 | 8 | 8 | 11 | 11 | 15 | 26 | 32 |
| Turbine Plant | | 3 | 8 | 8 | 8 | 8 | 8 | 8 | 11 | 11 | 7 | 14 | 17 |
| Cooling Tower | | | | | | | | | | | 3 | 4 | 6 |
| Water treatment plant | | | | | | | | | | | 5 | 8 | 9 |
| Turbine Plant | | | | | | | | | | | | | |
| Cooling Tower | | | | | | | | | | | | | |
| Water treatment plant | | | | | | | | | | | | | |
| Piping Inspector | | | | | | | | | 5 | 5 | 11 | 20 | 22 |
| Steam Generator Plant and Turbine Plant | | | | | | | | | | | 6 | 12 | 13 |
| Cooling Tower and Water Treatment Plant | | | | | | | | | 5 | 5 | 5 | 8 | 9 |
| Steam Generator Plant and Turbine Plant | | | | | | | | | | | | | |
| Cooling Tower and Water Treatment Plant | | | | | | | | | | | | | |
| MEQI Inspector | | | | | | | 4 | 4 | 9 | 12 | 12 | 19 | 21 |
| NDT for Plants | | | | | | | | | 3 | 4 | 4 | 7 | 8 |
| Tank | | | | | | | 4 | 4 | 6 | 8 | 8 | 12 | 13 |
| NDT for Plants | | | | | | | | | | | | | |
| Tank | | | | | | | | | | | | | |
| Total | | 6 | 11 | 11 | 13 | 17 | 23 | 23 | 36 | 39 | 52 | 80 | 90 |

Table 4.2: The resource utilization of the existing model

| | Aug '98 | Sep '98 | Oct '98 | Nov '98 | Dec '98 | Jan '99 | Feb '99 | Mar '99 | Apr '99 | May '99 | Jun '99 | Jul '99 | Aug '99 |
|---|------------|------------|------------|------------|------------|------------|------------|------------|------------|------------|------------|------------|------------|
| Steam Generator Inspector | 17 | 17 | 17 | 20 | 20 | 20 | 20 | 20 | 20 | 20 | 20 | 20 | 22 |
| Structural Steel and Duct | 7 | 7 | 7 | 9 | 9 | 9 | 9 | 9 | 9 | 9 | 9 | 9 | 9 |
| Pressure part | 10 | 10 | 10 | 11 | 11 | 11 | 11 | 11 | 11 | 11 | 11 | 11 | 11 |
| Structural Steel and Duct | | | | | | | | | | | | | 2 |
| Pressure part | | | | | | | | | | | | | |
| Mechanical Machine Inspector | 37 | 39 | 41 | 44 | 46 | 46 | 48 | 48 | 48 | 48 | 48 | 48 | 48 |
| Turbine Plant | 19 | 20 | 21 | 22 | 23 | 23 | 24 | 24 | 24 | 24 | 24 | 24 | 24 |
| Cooling Tower | 8 | 8 | 8 | 8 | 9 | 9 | 9 | 9 | 9 | 9 | 9 | 9 | 9 |
| Water treatment plant | 10 | 11 | 12 | 14 | 14 | 14 | 15 | 15 | 15 | 15 | 15 | 15 | 14 |
| Turbine Plant | | | | | | | | | | | | | 1 |
| Cooling Tower | | | | | | | | | | | | | |
| Water treatment plant | | | | | | | | | | | | | |
| Piping Inspector | 25 | 25 | 28 | 29 | 31 | 31 | 31 | 31 | 31 | 31 | 31 | 31 | 31 |
| Steam Generator Plant and Turbine Plant | 14 | 14 | 16 | 17 | 18 | 18 | 18 | 18 | 18 | 18 | 18 | 18 | 18 |
| Cooling Tower and Water Treatment Plant | 11 | 11 | 12 | 12 | 13 | 13 | 13 | 13 | 13 | 13 | 13 | 13 | 13 |
| Steam Generator Plant and Turbine Plant | | | | | | | | | | | | | |
| Cooling Tower and Water Treatment Plant | | | | | | | | | | | | | |
| MEQI Inspector | 21 | 22 | 23 | 23 | 23 | 23 | 23 | 23 | 23 | 21 | 21 | 21 | 21 |
| NDT for Plants | 8 | 8 | 9 | 9 | 9 | 8 | 8 | 8 | 8 | 6 | 6 | 7 | 7 |
| Tank | 13 | 14 | 14 | 14 | 14 | 15 | 15 | 15 | 15 | 15 | 15 | 14 | 14 |
| NDT for Plants | | | | | | | | | | | | | |
| Tank | | | | | | | | | | | | | |
| Total | 100 | 103 | 109 | 116 | 120 | 120 | 122 | 122 | 122 | 120 | 120 | 120 | 122 |

Table 4.2: The resource utilization of the existing model

| | Sep '99 | Oct '99 | Nov '99 | Dec '99 | Jan '00 | Feb '00 | Mar '00 | Apr '00 | May '00 | Jun '00 | Jul '00 | Aug '00 | Sep '00 |
|---|------------|------------|------------|------------|------------|------------|------------|------------|------------|-----------|-----------|-----------|-----------|
| Steam Generator Inspector | 22 | 22 | 23 | 23 | 26 | 27 | 27 | 24 | 19 | 20 | 19 | 18 | 10 |
| Structural Steel and Duct | 9 | 9 | 9 | 9 | 9 | 9 | 9 | 9 | | | | | |
| Pressure part | 11 | 11 | 11 | 11 | 11 | 11 | 11 | 8 | 10 | 10 | 8 | 6 | |
| Structural Steel and Duct | 2 | 2 | 3 | 3 | 3 | 4 | 4 | 4 | 4 | 4 | 5 | 5 | 5 |
| Pressure part | | | | | 3 | 3 | 3 | 3 | 5 | 6 | 6 | 7 | 5 |
| Mechanical Machine Inspector | 52 | 52 | 51 | 50 | 46 | 42 | 40 | 34 | 36 | 32 | 30 | 27 | 30 |
| Turbine Plant | 24 | 24 | 24 | 23 | 20 | 18 | 18 | 14 | 14 | 12 | 7 | | |
| Cooling Tower | 8 | 8 | 8 | 8 | 8 | 7 | 6 | 5 | 1 | | | | |
| Water treatment plant | 14 | 14 | 13 | 13 | 12 | 10 | 9 | 7 | 6 | | | | |
| Turbine Plant | 6 | 6 | 6 | 6 | 6 | 7 | 7 | 8 | 8 | 8 | 9 | 10 | 12 |
| Cooling Tower | | | | | | | | | 3 | 5 | 7 | 9 | 9 |
| Water treatment plant | | | | | | | | | 4 | 7 | 7 | 8 | 9 |
| Piping Inspector | 31 | 31 | 31 | 31 | 31 | 31 | 35 | 29 | 29 | 24 | 16 | 18 | 19 |
| Steam Generator Plant and Turbine Plant | 18 | 18 | 18 | 18 | 18 | 18 | 18 | 14 | 12 | 10 | | | |
| Cooling Tower and Water Treatment Plant | 13 | 13 | 13 | 13 | 13 | 13 | 13 | 11 | 9 | | | | |
| Steam Generator Plant and Turbine Plant | | | | | | | | | 4 | 8 | 9 | 10 | 10 |
| Cooling Tower and Water Treatment Plant | | | | | | | 4 | 4 | 4 | 6 | 7 | 8 | 9 |
| MEQI Inspector | 21 | 21 | 21 | 21 | 20 | 16 | 21 | 21 | 16 | 16 | 15 | 16 | 17 |
| NDT for Plants | 7 | | | | | | | | | | | | |
| Tank | 14 | 21 | 21 | 21 | 18 | 14 | 14 | 12 | 6 | 4 | | | |
| NDT for Plants | | | | | | | 4 | 6 | 6 | 8 | 9 | 10 | 10 |
| Tank | | | | | 2 | 2 | 3 | 3 | 4 | 4 | 6 | 6 | 7 |
| Total | 126 | 126 | 126 | 125 | 123 | 116 | 123 | 108 | 100 | 92 | 80 | 79 | 76 |

Table 4.2: The resource utilization of the existing model

| | Oct '00 | Nov '00 | Dec '00 | Jan '01 | Feb '01 | Mar '01 | Apr '01 | May '01 | Jun '01 | Jul '01 | Aug '01 | Sep '01 | Oct '01 |
|---|-----------|-----------|-----------|-----------|-----------|------------|------------|------------|------------|------------|------------|------------|------------|
| Steam Generator Inspector | 13 | 14 | 15 | 15 | 15 | 15 | 15 | 15 | 15 | 15 | 15 | 15 | 16 |
| Structural Steel and Duct | | | | | | | | | | | | | |
| Pressure part | | | | | | | | | | | | | |
| Structural Steel and Duct | 5 | 5 | 6 | 6 | 6 | 6 | 6 | 6 | 6 | 6 | 6 | 6 | 7 |
| Pressure part | 8 | 9 | 9 | 9 | 9 | 9 | 9 | 9 | 9 | 9 | 9 | 9 | 9 |
| Mechanical Machine Inspector | 32 | 33 | 34 | 36 | 37 | 39 | 39 | 39 | 39 | 39 | 39 | 39 | 39 |
| Turbine Plant | | | | | | | | | | | | | |
| Cooling Tower | | | | | | | | | | | | | |
| Water treatment plant | | | | | | | | | | | | | |
| Turbine Plant | 14 | 15 | 15 | 15 | 15 | 16 | 16 | 16 | 16 | 16 | 16 | 16 | 16 |
| Cooling Tower | 9 | 9 | 9 | 9 | 9 | 10 | 10 | 10 | 10 | 10 | 10 | 10 | 10 |
| Water treatment plant | 9 | 9 | 10 | 12 | 13 | 13 | 13 | 13 | 13 | 13 | 13 | 13 | 13 |
| Piping Inspector | 20 | 23 | 26 | 27 | 27 | 27 | 27 | 27 | 28 | 28 | 28 | 28 | 28 |
| Steam Generator Plant and Turbine Plant | | | | | | | | | | | | | |
| Cooling Tower and Water Treatment Plant | | | | | | | | | | | | | |
| Steam Generator Plant and Turbine Plant | 10 | 12 | 14 | 14 | 14 | 14 | 14 | 14 | 15 | 15 | 15 | 15 | 15 |
| Cooling Tower and Water Treatment Plant | 10 | 11 | 12 | 13 | 13 | 13 | 13 | 13 | 13 | 13 | 13 | 13 | 13 |
| MEQI Inspector | 18 | 19 | 20 | 20 | 20 | 20 | 20 | 20 | 20 | 19 | 19 | 19 | 19 |
| NDT for Plants | | | | | | | | | | | | | |
| Tank | | | | | | | | | | | | | |
| NDT for Plants | 10 | 11 | 12 | 12 | 12 | 12 | 12 | 12 | 12 | 11 | 11 | 11 | 11 |
| Tank | 8 | 8 | 8 | 8 | 8 | 8 | 8 | 8 | 8 | 8 | 8 | 8 | 8 |
| Total | 83 | 89 | 95 | 98 | 99 | 101 | 101 | 101 | 102 | 101 | 101 | 101 | 102 |

Table 4.2: The resource utilization of the existing model

| | Nov '01 | Dec '01 | Jan '02 | Feb '02 | Mar '02 | Apr '02 | May '02 | Jun '02 | Jul '02 | Aug '02 | Sep '02 | Total |
|---|------------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|----------|----------|--------------|
| Steam Generator Inspector | 16 | 16 | 16 | 16 | 15 | 15 | 14 | 8 | 7 | 6 | 4 | 970 |
| Structural Steel and Duct | | | | | | | | | | | | 240 |
| Pressure part | | | | | | | | | | | | 313 |
| Structural Steel and Duct | 7 | 7 | 7 | 7 | 6 | 6 | 5 | | | | | 172 |
| Pressure part | 9 | 9 | 9 | 9 | 9 | 9 | 9 | 8 | 7 | 6 | 4 | 245 |
| Mechanical Machine Inspector | 39 | 38 | 32 | 29 | 23 | 18 | 15 | 5 | | | | 1,940 |
| Turbine Plant | | | | | | | | | | | | 605 |
| Cooling Tower | | | | | | | | | | | | 185 |
| Water treatment plant | | | | | | | | | | | | 299 |
| Turbine Plant | 16 | 16 | 16 | 15 | 11 | 9 | 9 | 5 | | | | 399 |
| Cooling Tower | 10 | 9 | 7 | 6 | 5 | 2 | | | | | | 197 |
| Water treatment plant | 13 | 13 | 9 | 8 | 7 | 7 | 6 | | | | | 255 |
| Piping Inspector | 28 | 28 | 28 | 28 | 26 | 19 | 15 | 9 | 4 | 2 | | 1,336 |
| Steam Generator Plant and Turbine Plant | | | | | | | | | | | | 416 |
| Cooling Tower and Water Treatment Plant | | | | | | | | | | | | 306 |
| Steam Generator Plant and Turbine Plant | 15 | 15 | 15 | 15 | 15 | 12 | 10 | 9 | 4 | 2 | | 334 |
| Cooling Tower and Water Treatment Plant | 13 | 13 | 13 | 13 | 11 | 7 | 5 | | | | | 280 |
| MEQI Inspector | 18 | 17 | 16 | 15 | 14 | 13 | 9 | 5 | 3 | | | 974 |
| NDT for Plants | | | | | | | | | | | | 134 |
| Tank | | | | | | | | | | | | 387 |
| NDT for Plants | 11 | 10 | 10 | 9 | 9 | 9 | 6 | 3 | 3 | | | 272 |
| Tank | 7 | 7 | 6 | 6 | 5 | 4 | 3 | 2 | | | | 181 |
| Total | 101 | 99 | 92 | 88 | 78 | 65 | 53 | 27 | 14 | 8 | 4 | 5,220 |

Table 4.3: Cost of the existing model

| | Jul '97 | Aug '97 | Sep '97 | Oct '97 | Nov '97 | Dec '97 |
|---|---------|--------------------|--------------------|--------------------|--------------------|--------------------|
| Steam Generator Inspector | | 131,404.80B | 144,545.28B | 151,115.52B | 219,008.00B | 365,743.36B |
| Structural Steel and Duct | | 131,404.80B | 144,545.28B | 151,115.52B | 219,008.00B | 251,859.20B |
| Pressure part | | | | | | 113,884.16B |
| Structural Steel and Duct | | | | | | |
| Pressure part | | | | | | |
| Mechanical Machine Inspector | | 128,707.20B | 377,541.12B | 394,702.08B | 343,219.20B | 394,702.08B |
| Turbine Plant | | 128,707.20B | 377,541.12B | 394,702.08B | 343,219.20B | 394,702.08B |
| Cooling Tower | | | | | | |
| Water treatment plant | | | | | | |
| Turbine Plant | | | | | | |
| Cooling Tower | | | | | | |
| Water treatment plant | | | | | | |
| Piping Inspector | | | | | | |
| Steam Generator Plant and Turbine Plant | | | | | | |
| Cooling Tower and Water Treatment Plant | | | | | | |
| Steam Generator Plant and Turbine Plant | | | | | | |
| Cooling Tower and Water Treatment Plant | | | | | | |
| MEQI Inspector | | | | | | |
| NDT for Plants | | | | | | |
| Tank | | | | | | |
| NDT for Plants | | | | | | |
| Tank | | | | | | |
| Total | | 260,112.00B | 522,086.40B | 545,817.60B | 562,227.20B | 760,445.44B |

Table 4.3: Cost of the existing model

| | Jan '98 | Feb '98 | Mar '98 | Apr '98 | May '98 | Jun '98 | Jul '98 |
|---|----------------------|----------------------|----------------------|----------------------|----------------------|----------------------|----------------------|
| Steam Generator Inspector | 529,999.36B | 481,817.60B | 529,999.36B | 529,999.36B | 643,883.52B | 722,726.40B | 755,577.60B |
| Structural Steel and Duct | 240,908.80B | 219,008.00B | 240,908.80B | 240,908.80B | 275,950.08B | 289,090.56B | 302,231.04B |
| Pressure part | 289,090.56B | 262,809.60B | 289,090.56B | 289,090.56B | 367,933.44B | 433,635.84B | 453,346.56B |
| Structural Steel and Duct | | | | | | | |
| Pressure part | | | | | | | |
| Mechanical Machine Inspector | 377,541.12B | 343,219.20B | 519,119.04B | 519,119.04B | 658,551.84B | 1,227,008.64B | 1,578,808.32B |
| Turbine Plant | 377,541.12B | 343,219.20B | 519,119.04B | 519,119.04B | 315,332.64B | 660,696.96B | 838,741.92B |
| Cooling Tower | | | | | 128,707.20B | 188,770.56B | 296,026.56B |
| Water treatment plant | | | | | 214,512.00B | 377,541.12B | 444,039.84B |
| Turbine Plant | | | | | | | |
| Cooling Tower | | | | | | | |
| Water treatment plant | | | | | | | |
| Piping Inspector | | | 238,436.00B | 238,436.00B | 357,654.00B | 953,744.00B | 1,096,805.60B |
| Steam Generator Plant and Turbine Plant | | | | | 130,056.00B | 572,246.40B | 648,112.40B |
| Cooling Tower and Water Treatment Plant | | | 238,436.00B | 238,436.00B | 227,598.00B | 381,497.60B | 448,693.20B |
| Steam Generator Plant and Turbine Plant | | | | | | | |
| Cooling Tower and Water Treatment Plant | | | | | | | |
| MEQI Inspector | 116,222.08B | 178,803.20B | 442,537.92B | 590,050.56B | 563,230.08B | 934,246.72B | 1,079,524.32B |
| NDT for Plants | | | 147,512.64B | 196,683.52B | 187,743.36B | 344,196.16B | 411,247.36B |
| Tank | 116,222.08B | 178,803.20B | 295,025.28B | 393,367.04B | 375,486.72B | 590,050.56B | 668,276.96B |
| NDT for Plants | | | | | | | |
| Tank | | | | | | | |
| Total | 1,023,762.56B | 1,003,840.00B | 1,730,092.32B | 1,877,604.96B | 2,223,319.44B | 3,837,725.76B | 4,510,715.84B |

Table 4.3: Cost of the existing model

| | Aug '98 | Sep '98 | Oct '98 | Nov '98 | Dec '98 | Jan '99 | Feb '99 |
|---|----------------------|----------------------|----------------------|----------------------|----------------------|----------------------|----------------------|
| Steam Generator Inspector | 781,858.56B | 819,089.92B | 819,089.92B | 919,833.60B | 1,007,436.80B | 919,833.60B | 876,032.00B |
| Structural Steel and Duct | 321,941.76B | 337,272.32B | 337,272.32B | 413,925.12B | 453,346.56B | 413,925.12B | 394,214.40B |
| Pressure part | 459,916.80B | 481,817.60B | 481,817.60B | 505,908.48B | 554,090.24B | 505,908.48B | 481,817.60B |
| Structural Steel and Duct | | | | | | | |
| Pressure part | | | | | | | |
| Mechanical Machine Inspector | 1,666,758.24B | 1,840,512.96B | 1,934,898.24B | 1,982,090.88B | 2,269,536.96B | 2,072,185.92B | 2,059,315.20B |
| Turbine Plant | 855,902.88B | 943,852.80B | 991,045.44B | 991,045.44B | 1,134,768.48B | 1,036,092.96B | 1,029,657.60B |
| Cooling Tower | 360,380.16B | 377,541.12B | 377,541.12B | 360,380.16B | 444,039.84B | 405,427.68B | 386,121.60B |
| Water treatment plant | 450,475.20B | 519,119.04B | 566,311.68B | 630,665.28B | 690,728.64B | 630,665.28B | 643,536.00B |
| Turbine Plant | | | | | | | |
| Cooling Tower | | | | | | | |
| Water treatment plant | | | | | | | |
| Piping Inspector | 1,137,990.00B | 1,192,180.00B | 1,335,241.60B | 1,320,068.40B | 1,545,498.80B | 1,411,107.60B | 1,343,912.00B |
| Steam Generator Plant and Turbine Plant | 637,274.40B | 667,620.80B | 762,995.20B | 773,833.20B | 897,386.40B | 819,352.80B | 780,336.00B |
| Cooling Tower and Water Treatment Plant | 500,715.60B | 524,559.20B | 572,246.40B | 546,235.20B | 648,112.40B | 591,754.80B | 563,576.00B |
| Steam Generator Plant and Turbine Plant | | | | | | | |
| Cooling Tower and Water Treatment Plant | | | | | | | |
| MEQI Inspector | 985,652.64B | 1,081,759.36B | 1,130,930.24B | 1,079,524.32B | 1,182,336.16B | 1,079,524.32B | 1,028,118.40B |
| NDT for Plants | 375,486.72B | 393,367.04B | 442,537.92B | 422,422.56B | 462,653.28B | 375,486.72B | 357,606.40B |
| Tank | 610,165.92B | 688,392.32B | 688,392.32B | 657,101.76B | 719,682.88B | 704,037.60B | 670,512.00B |
| NDT for Plants | | | | | | | |
| Tank | | | | | | | |
| Total | 4,572,259.44B | 4,933,542.24B | 5,220,160.00B | 5,301,517.20B | 6,004,808.72B | 5,482,651.44B | 5,307,377.60B |

Table 4.3: Cost of the existing model

| | Mar '99 | Apr '99 | May '99 | Jun '99 | Jul '99 | Aug '99 |
|---|----------------------|----------------------|----------------------|----------------------|----------------------|----------------------|
| Steam Generator Inspector | 1,007,436.80B | 963,635.20B | 919,833.60B | 963,635.20B | 963,635.20B | 1,051,238.40B |
| Structural Steel and Duct | 453,346.56B | 433,635.84B | 413,925.12B | 433,635.84B | 433,635.84B | 433,635.84B |
| Pressure part | 554,090.24B | 529,999.36B | 505,908.48B | 529,999.36B | 529,999.36B | 529,999.36B |
| Structural Steel and Duct | | | | | | 87,603.20B |
| Pressure part | | | | | | |
| Mechanical Machine Inspector | 2,368,212.48B | 2,265,246.72B | 2,162,280.96B | 2,265,246.72B | 2,265,246.72B | 2,325,310.08B |
| Turbine Plant | 1,184,106.24B | 1,132,623.36B | 1,081,140.48B | 1,132,623.36B | 1,132,623.36B | 1,132,623.36B |
| Cooling Tower | 444,039.84B | 424,733.76B | 405,427.68B | 424,733.76B | 424,733.76B | 424,733.76B |
| Water treatment plant | 740,066.40B | 707,889.60B | 675,712.80B | 707,889.60B | 707,889.60B | 660,696.96B |
| Turbine Plant | | | | | | 107,256.00B |
| Cooling Tower | | | | | | |
| Water treatment plant | | | | | | |
| Piping Inspector | 1,545,498.80B | 1,478,303.20B | 1,411,107.60B | 1,478,303.20B | 1,478,303.20B | 1,478,303.20B |
| Steam Generator Plant and Turbine Plant | 897,386.40B | 858,369.60B | 819,352.80B | 858,369.60B | 858,369.60B | 858,369.60B |
| Cooling Tower and Water Treatment Plant | 648,112.40B | 619,933.60B | 591,754.80B | 619,933.60B | 619,933.60B | 619,933.60B |
| Steam Generator Plant and Turbine Plant | | | | | | |
| Cooling Tower and Water Treatment Plant | | | | | | |
| MEQI Inspector | 1,182,336.16B | 1,130,930.24B | 985,652.64B | 1,032,588.48B | 1,032,588.48B | 1,032,588.48B |
| NDT for Plants | 411,247.36B | 393,367.04B | 281,615.04B | 295,025.28B | 344,196.16B | 344,196.16B |
| Tank | 771,088.80B | 737,563.20B | 704,037.60B | 737,563.20B | 688,392.32B | 688,392.32B |
| NDT for Plants | | | | | | |
| Tank | | | | | | |
| Total | 6,103,484.24B | 5,838,115.36B | 5,478,874.80B | 5,739,773.60B | 5,739,773.60B | 5,887,440.16B |

Table 4.3: Cost of the existing model

| | Sep '99 | Oct '99 | Nov '99 | Dec '99 | Jan '00 | Feb '00 |
|---|----------------------|----------------------|----------------------|----------------------|----------------------|----------------------|
| Steam Generator Inspector | 1,059,998.72B | 1,011,816.96B | 1,180,453.12B | 1,234,110.08B | 1,376,465.28B | 1,379,750.40B |
| Structural Steel and Duct | 433,635.84B | 413,925.12B | 433,635.84B | 453,346.56B | 413,925.12B | 413,925.12B |
| Pressure part | 529,999.36B | 505,908.48B | 529,999.36B | 554,090.24B | 505,908.48B | 505,908.48B |
| Structural Steel and Duct | 96,363.52B | 91,983.36B | 216,817.92B | 226,673.28B | 206,962.56B | 183,966.72B |
| Pressure part | | | | | 249,669.12B | 275,950.08B |
| Mechanical Machine Inspector | 2,524,806.24B | 2,410,042.32B | 2,477,613.60B | 2,540,894.64B | 2,139,757.20B | 1,891,995.84B |
| Turbine Plant | 1,132,623.36B | 1,081,140.48B | 1,132,623.36B | 1,134,768.48B | 900,950.40B | 810,855.36B |
| Cooling Tower | 377,541.12B | 360,380.16B | 377,541.12B | 394,702.08B | 360,380.16B | 315,332.64B |
| Water treatment plant | 660,696.96B | 630,665.28B | 613,504.32B | 641,390.88B | 540,570.24B | 450,475.20B |
| Turbine Plant | 353,944.80B | 337,856.40B | 353,944.80B | 370,033.20B | 337,856.40B | 315,332.64B |
| Cooling Tower | | | | | | |
| Water treatment plant | | | | | | |
| Piping Inspector | 1,478,303.20B | 1,411,107.60B | 1,478,303.20B | 1,545,498.80B | 1,411,107.60B | 1,411,107.60B |
| Steam Generator Plant and Turbine Plant | 858,369.60B | 819,352.80B | 858,369.60B | 897,386.40B | 819,352.80B | 819,352.80B |
| Cooling Tower and Water Treatment Plant | 619,933.60B | 591,754.80B | 619,933.60B | 648,112.40B | 591,754.80B | 591,754.80B |
| Steam Generator Plant and Turbine Plant | | | | | | |
| Cooling Tower and Water Treatment Plant | | | | | | |
| MEQI Inspector | 907,426.24B | 985,652.64B | 1,032,588.48B | 1,079,524.32B | 954,362.08B | 821,377.20B |
| NDT for Plants | 219,033.92B | | | | | |
| Tank | 688,392.32B | 985,652.64B | 1,032,588.48B | 1,079,524.32B | 844,845.12B | 657,101.76B |
| NDT for Plants | | | | | | |
| Tank | | | | | 109,516.96B | 164,275.44B |
| Total | 5,970,534.40B | 5,818,619.52B | 6,168,958.40B | 6,400,027.84B | 5,881,692.16B | 5,504,231.04B |

Table 4.3: Cost of the existing model

| | Mar '00 | Apr '00 | May '00 | Jun '00 | Jul '00 | Aug '00 |
|---|----------------------|----------------------|----------------------|----------------------|----------------------|----------------------|
| Steam Generator Inspector | 1,511,155.20B | 1,182,643.20B | 1,108,180.48B | 1,108,180.48B | 942,829.44B | 808,139.52B |
| Structural Steel and Duct | 453,346.56B | 394,214.40B | | | | |
| Pressure part | 554,090.24B | 350,412.80B | 503,718.40B | 481,817.60B | 367,933.44B | 52,561.92B |
| Structural Steel and Duct | 201,487.36B | 175,206.40B | 277,045.12B | 264,999.68B | 229,958.40B | 327,416.96B |
| Pressure part | 302,231.04B | 262,809.60B | 327,416.96B | 361,363.20B | 344,937.60B | 428,160.64B |
| Mechanical Machine Inspector | 2,047,517.04B | 1,587,388.80B | 1,790,102.64B | 1,651,742.40B | 1,456,536.48B | 1,628,146.08B |
| Turbine Plant | 888,079.68B | 600,633.60B | 690,728.64B | 566,311.68B | 150,158.40B | |
| Cooling Tower | 296,026.56B | 214,512.00B | 2,145.12B | | | |
| Water treatment plant | 444,039.84B | 300,316.80B | 283,155.84B | | | |
| Turbine Plant | 419,370.96B | 471,926.40B | 394,702.08B | 448,330.08B | 608,141.52B | 789,404.16B |
| Cooling Tower | | | 222,019.92B | 306,752.16B | 382,903.92B | 444,039.84B |
| Water treatment plant | | | 197,351.04B | 330,348.48B | 315,332.64B | 394,702.08B |
| Piping Inspector | 1,736,247.60B | 1,257,208.00B | 1,407,856.20B | 1,172,671.60B | 796,593.00B | 1,046,950.80B |
| Steam Generator Plant and Turbine Plant | 897,386.40B | 606,928.00B | 598,257.60B | 433,520.00B | | |
| Cooling Tower and Water Treatment Plant | 648,112.40B | 476,872.00B | 448,693.20B | | | |
| Steam Generator Plant and Turbine Plant | | | 86,704.00B | 381,497.60B | 409,676.40B | 498,548.00B |
| Cooling Tower and Water Treatment Plant | 190,748.80B | 173,408.00B | 274,201.40B | 357,654.00B | 386,916.60B | 548,402.80B |
| MEQI Inspector | 1,147,693.04B | 1,072,819.20B | 899,603.60B | 900,721.12B | 844,845.12B | 976,712.48B |
| NDT for Plants | | | | | | |
| Tank | 719,682.88B | 536,409.60B | 308,435.52B | 89,401.60B | | |
| NDT for Plants | 196,683.52B | 268,204.80B | 308,435.52B | 393,367.04B | 422,422.56B | 514,059.20B |
| Tank | 231,326.64B | 268,204.80B | 282,732.56B | 417,952.48B | 422,422.56B | 462,653.28B |
| Total | 6,442,612.88B | 5,100,059.20B | 5,205,742.92B | 4,833,315.60B | 4,040,804.04B | 4,459,948.88B |

Table 4.3: Cost of the existing model

| | Sep '00 | Oct '00 | Nov '00 | Dec '00 | Jan '01 | Feb '01 | Mar '01 |
|---|----------------------|----------------------|----------------------|----------------------|----------------------|----------------------|----------------------|
| Steam Generator Inspector | 735,866.88B | 698,635.52B | 891,362.56B | 827,850.24B | 906,693.12B | 788,428.80B | 939,544.32B |
| Structural Steel and Duct | | | | | | | |
| Pressure part | | | | | | | |
| Structural Steel and Duct | 298,945.92B | 313,181.44B | 385,454.08B | 344,937.60B | 377,788.80B | 328,512.00B | 361,363.20B |
| Pressure part | 436,920.96B | 385,454.08B | 505,908.48B | 482,912.64B | 528,904.32B | 459,916.80B | 578,181.12B |
| Mechanical Machine Inspector | 1,554,139.44B | 1,722,531.36B | 1,769,724.00B | 1,801,900.80B | 2,072,185.92B | 1,909,156.80B | 1,982,090.88B |
| Turbine Plant | | | | | | | |
| Cooling Tower | | | | | | | |
| Water treatment plant | | | | | | | |
| Turbine Plant | 743,284.08B | 802,274.88B | 778,678.56B | 810,855.36B | 888,079.68B | 836,596.80B | 896,660.16B |
| Cooling Tower | 405,427.68B | 495,522.72B | 566,311.68B | 540,570.24B | 592,053.12B | 514,828.80B | 471,926.40B |
| Water treatment plant | 405,427.68B | 424,733.76B | 424,733.76B | 450,475.20B | 592,053.12B | 557,731.20B | 613,504.32B |
| Piping Inspector | 933,151.80B | 1,025,274.80B | 1,168,336.40B | 1,251,789.00B | 1,346,079.60B | 1,170,504.00B | 1,287,554.40B |
| Steam Generator Plant and Turbine Plant | | | | | | | |
| Cooling Tower and Water Treatment Plant | | | | | | | |
| Steam Generator Plant and Turbine Plant | 455,196.00B | 476,872.00B | 572,246.40B | 637,274.40B | 697,967.20B | 606,928.00B | 667,620.80B |
| Cooling Tower and Water Treatment Plant | 477,955.80B | 548,402.80B | 596,090.00B | 614,514.60B | 648,112.40B | 563,576.00B | 619,933.60B |
| MEQI Inspector | 868,313.04B | 885,075.84B | 934,246.72B | 938,716.80B | 1,028,118.40B | 894,016.00B | 983,417.60B |
| NDT for Plants | | | | | | | |
| Tank | | | | | | | |
| NDT for Plants | 469,358.40B | 491,708.80B | 540,879.68B | 563,230.08B | 616,871.04B | 536,409.60B | 590,050.56B |
| Tank | 398,954.64B | 393,367.04B | 393,367.04B | 375,486.72B | 411,247.36B | 357,606.40B | 393,367.04B |
| Total | 4,091,471.16B | 4,331,517.52B | 4,763,669.68B | 4,820,256.84B | 5,353,077.04B | 4,762,105.60B | 5,192,607.20B |

Table 4.3: Cost of the existing model

| | Apr '01 | May '01 | Jun '01 | Jul '01 | Aug '01 | Sep '01 |
|---|----------------------|----------------------|----------------------|----------------------|----------------------|----------------------|
| Steam Generator Inspector | 896,837.76B | 906,693.12B | 827,850.24B | 867,271.68B | 906,693.12B | 788,428.80B |
| Structural Steel and Duct | | | | | | |
| Pressure part | | | | | | |
| Structural Steel and Duct | 344,937.60B | 377,788.80B | 344,937.60B | 361,363.20B | 377,788.80B | 328,512.00B |
| Pressure part | 551,900.16B | 528,904.32B | 482,912.64B | 505,908.48B | 528,904.32B | 459,916.80B |
| Mechanical Machine Inspector | 1,824,424.56B | 1,998,179.28B | 1,824,424.56B | 1,911,301.92B | 1,924,172.64B | 1,673,193.60B |
| Turbine Plant | | | | | | |
| Cooling Tower | | | | | | |
| Water treatment plant | | | | | | |
| Turbine Plant | 788,331.60B | 863,410.80B | 788,331.60B | 825,871.20B | 789,404.16B | 686,438.40B |
| Cooling Tower | 450,475.20B | 493,377.60B | 450,475.20B | 471,926.40B | 493,377.60B | 429,024.00B |
| Water treatment plant | 585,617.76B | 641,390.88B | 585,617.76B | 613,504.32B | 641,390.88B | 557,731.20B |
| Piping Inspector | 1,229,029.20B | 1,346,079.60B | 1,274,548.80B | 1,335,241.60B | 1,395,934.40B | 1,213,856.00B |
| Steam Generator Plant and Turbine Plant | | | | | | |
| Cooling Tower and Water Treatment Plant | | | | | | |
| Steam Generator Plant and Turbine Plant | 637,274.40B | 697,967.20B | 682,794.00B | 715,308.00B | 747,822.00B | 650,280.00B |
| Cooling Tower and Water Treatment Plant | 591,754.80B | 648,112.40B | 591,754.80B | 619,933.60B | 648,112.40B | 563,576.00B |
| MEQI Inspector | 938,716.80B | 1,028,118.40B | 938,716.80B | 934,246.72B | 976,712.48B | 849,315.20B |
| NDT for Plants | | | | | | |
| Tank | | | | | | |
| NDT for Plants | 563,230.08B | 616,871.04B | 563,230.08B | 540,879.68B | 565,465.12B | 491,708.80B |
| Tank | 375,486.72B | 411,247.36B | 375,486.72B | 393,367.04B | 411,247.36B | 357,606.40B |
| Total | 4,889,008.32B | 5,279,070.40B | 4,865,540.40B | 5,048,061.92B | 5,203,512.64B | 4,524,793.60B |

Table 4.3: Cost of the existing model

| | Oct '01 | Nov '01 | Dec '01 | Jan '02 | Feb '02 | Mar '02 | Apr '02 |
|---|---------------|---------------|---------------|---------------|---------------|---------------|---------------|
| Steam Generator Inspector | 881,507.20B | 843,180.80B | 804,854.40B | 881,507.20B | 766,528.00B | 689,875.20B | 722,726.40B |
| Structural Steel and Duct | | | | | | | |
| Pressure part | | | | | | | |
| Structural Steel and Duct | 352,602.88B | 337,272.32B | 321,941.76B | 352,602.88B | 306,611.20B | 275,950.08B | 289,090.56B |
| Pressure part | 528,904.32B | 505,908.48B | 482,912.64B | 528,904.32B | 459,916.80B | 413,925.12B | 433,635.84B |
| Mechanical Machine Inspector | 1,924,172.64B | 1,840,512.96B | 1,711,805.76B | 1,578,808.32B | 1,244,169.60B | 785,099.17B | 849,656.55B |
| Turbine Plant | | | | | | | |
| Cooling Tower | | | | | | | |
| Water treatment plant | | | | | | | |
| Turbine Plant | 789,404.16B | 755,082.24B | 720,760.32B | 789,404.16B | 643,536.00B | 495,522.72B | 424,733.76B |
| Cooling Tower | 493,377.60B | 471,926.40B | 405,427.68B | 345,364.32B | 257,414.40B | 122,271.84B | 94,410.96B |
| Water treatment plant | 641,390.88B | 613,504.32B | 585,617.76B | 444,039.84B | 343,219.20B | 167,304.61B | 330,511.82B |
| Piping Inspector | 1,395,934.40B | 1,335,241.60B | 1,274,548.80B | 1,395,934.40B | 1,213,856.00B | 1,183,509.60B | 906,056.80B |
| Steam Generator Plant and Turbine Plant | | | | | | | |
| Cooling Tower and Water Treatment Plant | | | | | | | |
| Steam Generator Plant and Turbine Plant | 747,822.00B | 715,308.00B | 682,794.00B | 747,822.00B | 650,280.00B | 682,794.00B | 572,246.40B |
| Cooling Tower and Water Treatment Plant | 648,112.40B | 619,933.60B | 591,754.80B | 648,112.40B | 563,576.00B | 500,715.60B | 333,810.40B |
| MEQI Inspector | 976,712.48B | 885,075.84B | 797,909.28B | 822,494.72B | 670,512.00B | 657,101.76B | 639,221.44B |
| NDT for Plants | | | | | | | |
| Tank | | | | | | | |
| NDT for Plants | 565,465.12B | 540,879.68B | 469,358.40B | 514,059.20B | 402,307.20B | 422,422.56B | 442,537.92B |
| Tank | 411,247.36B | 344,196.16B | 328,550.88B | 308,435.52B | 268,204.80B | 234,679.20B | 196,683.52B |
| Total | 5,178,326.72B | 4,904,011.20B | 4,589,118.24B | 4,678,744.64B | 3,895,065.60B | 3,315,585.73B | 3,117,661.19B |

Table 4.3: Cost of the existing model

| | May '02 | Jun '02 | Jul '02 | Aug '02 | Sep '02 | Total |
|---|----------------------|----------------------|--------------------|--------------------|--------------------|------------------------|
| Steam Generator Inspector | 606,652.16B | 350,412.80B | 352,602.88B | 289,090.56B | 148,903.54B | 49,442,129.14B |
| Structural Steel and Duct | | | | | | 11,390,606.08B |
| Pressure part | | | | | | 14,592,503.04B |
| Structural Steel and Duct | 153,305.60B | | | | | 9,521,372.80B |
| Pressure part | 453,346.56B | 350,412.80B | 352,602.88B | 289,090.56B | 148,903.54B | 13,937,647.22B |
| Mechanical Machine Inspector | 740,054.35B | 214,512.00B | | | | 93,341,841.35B |
| Turbine Plant | | | | | | 28,079,620.80B |
| Cooling Tower | | | | | | 8,571,899.52B |
| Water treatment plant | | | | | | 13,932,554.40B |
| Turbine Plant | 444,039.84B | 214,512.00B | | | | 21,083,311.92B |
| Cooling Tower | | | | | | 9,921,205.68B |
| Water treatment plant | 296,014.51B | | | | | 11,753,249.02B |
| Piping Inspector | 661,118.00B | 390,168.00B | 199,419.20B | 86,695.87B | | 63,213,710.67B |
| Steam Generator Plant and Turbine Plant | | | | | | 19,447,707.20B |
| Cooling Tower and Water Treatment Plant | | | | | | 14,438,383.60B |
| Steam Generator Plant and Turbine Plant | 498,548.00B | 390,168.00B | 199,419.20B | 86,695.87B | | 15,595,873.87B |
| Cooling Tower and Water Treatment Plant | 162,570.00B | | | | | 13,731,746.00B |
| MEQI Inspector | 462,653.28B | 201,153.60B | 33,525.60B | | | 47,836,561.12B |
| NDT for Plants | | | | | | 6,405,624.64B |
| Tank | | | | | | 18,624,588.32B |
| NDT for Plants | 308,435.52B | 134,102.40B | 33,525.60B | | | 13,086,159.20B |
| Tank | 154,217.76B | 67,051.20B | | | | 9,720,188.96B |
| Total | 2,470,477.79B | 1,156,246.40B | 585,547.68B | 375,786.43B | 148,903.54B | 253,834,242.28B |

Table 4.4: The resource utilization of the proposed model

| | Jul '97 | Aug '97 | Sep '97 | Oct '97 | Nov '97 | Dec '97 | Jan '98 | Feb '98 | Mar '98 | Apr '98 | May '98 | Jun '98 | Jul '98 |
|---|---------|----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| Steam Generator Inspector | | 3 | 3 | 3 | 5 | 9 | 11 | 11 | 11 | 11 | 14 | 15 | 15 |
| Structural Steel and Duct | | 3 | 3 | 3 | 5 | 5 | 5 | 5 | 5 | 5 | 6 | 6 | 6 |
| Pressure part | | | | | | 4 | 6 | 6 | 6 | 6 | 8 | 9 | 9 |
| Structural Steel and Duct | | | | | | | | | | | | | |
| Pressure part | | | | | | | | | | | | | |
| Mechanical Machine Inspector | | 3 | 8 | 8 | 8 | 8 | 8 | 8 | 11 | 11 | 15 | 26 | 32 |
| Turbine Plant | | 3 | 8 | 8 | 8 | 8 | 8 | 8 | 11 | 11 | 7 | 14 | 17 |
| Cooling Tower | | | | | | | | | | | 3 | 4 | 6 |
| Water treatment plant | | | | | | | | | | | 5 | 8 | 9 |
| Turbine Plant | | | | | | | | | | | | | |
| Cooling Tower | | | | | | | | | | | | | |
| Water treatment plant | | | | | | | | | | | | | |
| Piping Inspector | | | | | | | | | 5 | 5 | 11 | 20 | 22 |
| Steam Generator Plant and Turbine Plant | | | | | | | | | | | 6 | 12 | 13 |
| Cooling Tower and Water Treatment Plant | | | | | | | | | 5 | 5 | 5 | 8 | 9 |
| Steam Generator Plant and Turbine Plant | | | | | | | | | | | | | |
| Cooling Tower and Water Treatment Plant | | | | | | | | | | | | | |
| MEQI Inspector | | | | | | | 4 | 4 | 9 | 12 | 12 | 19 | 21 |
| NDT for Plants | | | | | | | | | 3 | 4 | 4 | 7 | 8 |
| Tank | | | | | | | 4 | 4 | 6 | 8 | 8 | 12 | 13 |
| NDT for Plants | | | | | | | | | | | | | |
| Tank | | | | | | | | | | | | | |
| Total | | 6 | 11 | 11 | 13 | 17 | 23 | 23 | 36 | 39 | 52 | 80 | 90 |

Table 4.4: The resource utilization of the proposed model

| | Aug '98 | Sep '98 | Oct '98 | Nov '98 | Dec '98 | Jan '99 | Feb '99 | Mar '99 | Apr '99 | May '99 | Jun '99 | Jul '99 | Aug '99 |
|---|------------|------------|------------|------------|------------|------------|------------|------------|------------|------------|------------|------------|------------|
| Steam Generator Inspector | 17 | 17 | 17 | 20 | 20 | 20 | 20 | 20 | 20 | 20 | 20 | 20 | 22 |
| Structural Steel and Duct | 7 | 7 | 7 | 9 | 9 | 9 | 9 | 9 | 9 | 9 | 9 | 9 | 9 |
| Pressure part | 10 | 10 | 10 | 11 | 11 | 11 | 11 | 11 | 11 | 11 | 11 | 11 | 11 |
| Structural Steel and Duct | | | | | | | | | | | | | 2 |
| Pressure part | | | | | | | | | | | | | |
| Mechanical Machine Inspector | 37 | 39 | 41 | 44 | 46 | 46 | 48 | 48 | 45 | 45 | 45 | 45 | 43 |
| Turbine Plant | 19 | 20 | 21 | 22 | 23 | 23 | 24 | 24 | 23 | 23 | 23 | 23 | 22 |
| Cooling Tower | 8 | 8 | 8 | 8 | 9 | 9 | 9 | 9 | 8 | 8 | 8 | 8 | 7 |
| Water treatment plant | 10 | 11 | 12 | 14 | 14 | 14 | 15 | 15 | 14 | 14 | 14 | 14 | 12 |
| Turbine Plant | | | | | | | | | | | | | 2 |
| Cooling Tower | | | | | | | | | | | | | |
| Water treatment plant | | | | | | | | | | | | | |
| Piping Inspector | 25 | 25 | 28 | 29 | 31 | 31 | 31 | 31 | 31 | 31 | 31 | 31 | 31 |
| Steam Generator Plant and Turbine Plant | 14 | 14 | 16 | 17 | 18 | 18 | 18 | 18 | 18 | 18 | 18 | 18 | 18 |
| Cooling Tower and Water Treatment Plant | 11 | 11 | 12 | 12 | 13 | 13 | 13 | 13 | 13 | 13 | 13 | 13 | 13 |
| Steam Generator Plant and Turbine Plant | | | | | | | | | | | | | |
| Cooling Tower and Water Treatment Plant | | | | | | | | | | | | | |
| MEQI Inspector | 21 | 22 | 23 | 23 | 23 | 23 | 23 | 23 | 23 | 21 | 21 | 21 | 21 |
| NDT for Plants | 8 | 8 | 9 | 9 | 9 | 8 | 8 | 8 | 8 | 6 | 6 | 7 | 7 |
| Tank | 13 | 14 | 14 | 14 | 14 | 15 | 15 | 15 | 15 | 15 | 15 | 14 | 14 |
| NDT for Plants | | | | | | | | | | | | | |
| Tank | | | | | | | | | | | | | |
| Total | 100 | 103 | 109 | 116 | 120 | 120 | 122 | 122 | 119 | 117 | 117 | 117 | 117 |

Table 4.4: The resource utilization of the proposed model

| | Sep '99 | Oct '99 | Nov '99 | Dec '99 | Jan '00 | Feb '00 | Mar '00 | Apr '00 | May '00 | Jun '00 | Jul '00 | Aug '00 | Sep '00 |
|---|------------|------------|------------|------------|------------|------------|------------|-----------|-----------|-----------|-----------|-----------|-----------|
| Steam Generator Inspector | 22 | 22 | 24 | 24 | 29 | 29 | 23 | 22 | 17 | 16 | 15 | 15 | 14 |
| Structural Steel and Duct | 9 | 9 | 9 | 9 | 9 | 9 | 6 | 5 | | | | | |
| Pressure part | 11 | 11 | 11 | 11 | 11 | 11 | 8 | 8 | 6 | 4 | 3 | 1 | |
| Structural Steel and Duct | 2 | 2 | 4 | 4 | 4 | 4 | 4 | 4 | 5 | 5 | 5 | 6 | 6 |
| Pressure part | | | | | 5 | 5 | 5 | 5 | 6 | 7 | 7 | 8 | 8 |
| Mechanical Machine Inspector | 48 | 48 | 48 | 45 | 37 | 33 | 33 | 28 | 29 | 32 | 32 | 34 | 36 |
| Turbine Plant | 22 | 22 | 22 | 21 | 16 | 14 | 14 | 12 | 11 | 9 | 3 | | |
| Cooling Tower | 7 | 7 | 7 | 6 | 6 | 5 | 4 | 2 | 1 | | | | |
| Water treatment plant | 12 | 12 | 12 | 11 | 8 | 7 | 7 | 4 | 3 | | | | |
| Turbine Plant | 7 | 7 | 7 | 7 | 7 | 7 | 8 | 10 | 6 | 9 | 12 | 14 | 15 |
| Cooling Tower | | | | | | | | | 4 | 6 | 8 | 9 | 9 |
| Water treatment plant | | | | | | | | | 4 | 8 | 9 | 11 | 12 |
| Piping Inspector | 31 | 31 | 31 | 31 | 30 | 29 | 32 | 23 | 26 | 24 | 18 | 22 | 22 |
| Steam Generator Plant and Turbine Plant | 18 | 18 | 18 | 18 | 18 | 17 | 17 | 11 | 9 | 8 | | | |
| Cooling Tower and Water Treatment Plant | 13 | 13 | 13 | 13 | 12 | 12 | 11 | 8 | 7 | | | | |
| Steam Generator Plant and Turbine Plant | | | | | | | | | 5 | 9 | 10 | 12 | 12 |
| Cooling Tower and Water Treatment Plant | | | | | | | 4 | 4 | 5 | 7 | 8 | 10 | 10 |
| MEQI Inspector | 21 | 21 | 21 | 20 | 17 | 14 | 19 | 20 | 15 | 20 | 18 | 18 | 19 |
| NDT for Plants | 7 | | | | | | | | | | | | |
| Tank | 14 | 21 | 21 | 20 | 14 | 11 | 11 | 9 | 4 | 4 | | | |
| NDT for Plants | | | | | | | 4 | 6 | 6 | 9 | 10 | 10 | 11 |
| Tank | | | | | 3 | 3 | 4 | 5 | 5 | 7 | 8 | 8 | 8 |
| Total | 122 | 122 | 124 | 120 | 113 | 105 | 107 | 93 | 87 | 92 | 83 | 89 | 91 |

Table 4.4: The resource utilization of the proposed model

| | Oct '00 | Nov '00 | Dec '00 | Jan '01 | Feb '01 | Mar '01 | Apr '01 | May '01 | Jun '01 | Jul '01 | Aug '01 | Sep '01 | Oct '01 |
|---|-----------|------------|------------|------------|------------|------------|------------|------------|------------|------------|------------|------------|------------|
| Steam Generator Inspector | 14 | 17 | 17 | 17 | 17 | 18 | 18 | 17 | 17 | 17 | 17 | 17 | 17 |
| Structural Steel and Duct | | | | | | | | | | | | | |
| Pressure part | | | | | | | | | | | | | |
| Structural Steel and Duct | 6 | 7 | 7 | 7 | 7 | 7 | 7 | 7 | 7 | 7 | 7 | 7 | 7 |
| Pressure part | 8 | 10 | 10 | 10 | 10 | 11 | 11 | 10 | 10 | 10 | 10 | 10 | 10 |
| Mechanical Machine Inspector | 38 | 39 | 41 | 41 | 43 | 42 | 40 | 40 | 40 | 40 | 38 | 38 | 38 |
| Turbine Plant | | | | | | | | | | | | | |
| Cooling Tower | | | | | | | | | | | | | |
| Water treatment plant | | | | | | | | | | | | | |
| Turbine Plant | 16 | 16 | 17 | 17 | 18 | 18 | 17 | 17 | 17 | 17 | 16 | 16 | 16 |
| Cooling Tower | 10 | 11 | 11 | 11 | 11 | 10 | 10 | 10 | 10 | 10 | 9 | 9 | 9 |
| Water treatment plant | 12 | 12 | 13 | 13 | 14 | 14 | 13 | 13 | 13 | 13 | 13 | 13 | 13 |
| Piping Inspector | 25 | 26 | 28 | 28 | 28 | 28 | 28 | 28 | 28 | 28 | 28 | 28 | 28 |
| Steam Generator Plant and Turbine Plant | | | | | | | | | | | | | |
| Cooling Tower and Water Treatment Plant | | | | | | | | | | | | | |
| Steam Generator Plant and Turbine Plant | 14 | 14 | 15 | 15 | 15 | 15 | 15 | 15 | 15 | 15 | 15 | 15 | 15 |
| Cooling Tower and Water Treatment Plant | 11 | 12 | 13 | 13 | 13 | 13 | 13 | 13 | 13 | 13 | 13 | 13 | 13 |
| MEQI Inspector | 20 | 20 | 20 | 20 | 20 | 20 | 20 | 18 | 18 | 18 | 18 | 18 | 18 |
| NDT for Plants | | | | | | | | | | | | | |
| Tank | | | | | | | | | | | | | |
| NDT for Plants | 12 | 12 | 12 | 12 | 12 | 12 | 12 | 11 | 11 | 11 | 11 | 11 | 11 |
| Tank | 8 | 8 | 8 | 8 | 8 | 8 | 8 | 7 | 7 | 7 | 7 | 7 | 7 |
| Total | 97 | 102 | 106 | 106 | 108 | 108 | 106 | 103 | 103 | 103 | 101 | 101 | 101 |

Table 4.4: The resource utilization of the proposed model

| | Nov '01 | Dec '01 | Jan '02 | Feb '02 | Mar '02 | Apr '02 | May '02 | Jun '02 | Jul '02 | Aug '02 | Sep '02 | Total |
|---|------------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|----------|----------|----------|--------------|
| Steam Generator Inspector | 17 | 17 | 17 | 17 | 13 | 11 | 9 | 5 | 5 | 4 | 1 | 972 |
| Structural Steel and Duct | | | | | | | | | | | | 233 |
| Pressure part | | | | | | | | | | | | 290 |
| Structural Steel and Duct | 7 | 7 | 7 | 7 | 5 | 5 | 4 | | | | | 189 |
| Pressure part | 10 | 10 | 10 | 10 | 8 | 6 | 5 | 5 | 5 | 4 | 1 | 260 |
| Mechanical Machine Inspector | 38 | 34 | 27 | 22 | 20 | 16 | 15 | 3 | | | | 1,894 |
| Turbine Plant | | | | | | | | | | | | 567 |
| Cooling Tower | | | | | | | | | | | | 165 |
| Water treatment plant | | | | | | | | | | | | 271 |
| Turbine Plant | 16 | 14 | 14 | 12 | 11 | 9 | 9 | 3 | | | | 424 |
| Cooling Tower | 9 | 8 | 7 | 4 | 3 | 1 | | | | | | 199 |
| Water treatment plant | 13 | 12 | 6 | 6 | 6 | 6 | 6 | | | | | 268 |
| Piping Inspector | 28 | 28 | 27 | 26 | 24 | 16 | 14 | 8 | 1 | 1 | | 1,331 |
| Steam Generator Plant and Turbine Plant | | | | | | | | | | | | 406 |
| Cooling Tower and Water Treatment Plant | | | | | | | | | | | | 297 |
| Steam Generator Plant and Turbine Plant | 15 | 15 | 15 | 14 | 14 | 10 | 9 | 8 | 1 | 1 | | 343 |
| Cooling Tower and Water Treatment Plant | 13 | 13 | 12 | 12 | 10 | 6 | 5 | | | | | 285 |
| MEQI Inspector | 18 | 16 | 16 | 12 | 10 | 10 | 6 | 3 | 2 | | | 953 |
| NDT for Plants | | | | | | | | | | | | 134 |
| Tank | | | | | | | | | | | | 371 |
| NDT for Plants | 11 | 10 | 10 | 7 | 7 | 7 | 4 | 2 | 2 | | | 266 |
| Tank | 7 | 6 | 6 | 5 | 3 | 3 | 2 | 1 | | | | 182 |
| Total | 101 | 95 | 87 | 77 | 67 | 53 | 44 | 19 | 8 | 5 | 1 | 5,150 |

Table 4.5: Cost of the proposed model

| | Jul '97 | Aug '97 | Sep '97 | Oct '97 | Nov '97 | Dec '97 |
|---|---------|--------------------|--------------------|--------------------|--------------------|--------------------|
| Steam Generator Inspector | | 131,404.80B | 144,545.28B | 151,115.52B | 219,008.00B | 365,743.36B |
| Structural Steel and Duct | | 131,404.80B | 144,545.28B | 151,115.52B | 219,008.00B | 251,859.20B |
| Pressure part | | | | | | 113,884.16B |
| Structural Steel and Duct | | | | | | |
| Pressure part | | | | | | |
| Mechanical Machine Inspector | | 128,707.20B | 377,541.12B | 394,702.08B | 343,219.20B | 394,702.08B |
| Turbine Plant | | 128,707.20B | 377,541.12B | 394,702.08B | 343,219.20B | 394,702.08B |
| Cooling Tower | | | | | | |
| Water treatment plant | | | | | | |
| Turbine Plant | | | | | | |
| Cooling Tower | | | | | | |
| Water treatment plant | | | | | | |
| Piping Inspector | | | | | | |
| Steam Generator Plant and Turbine Plant | | | | | | |
| Cooling Tower and Water Treatment Plant | | | | | | |
| Steam Generator Plant and Turbine Plant | | | | | | |
| Cooling Tower and Water Treatment Plant | | | | | | |
| MEQI Inspector | | | | | | |
| NDT for Plants | | | | | | |
| Tank | | | | | | |
| NDT for Plants | | | | | | |
| Tank | | | | | | |
| Total | | 260,112.00B | 522,086.40B | 545,817.60B | 562,227.20B | 760,445.44B |

Table 4.5: Cost of the proposed model

| | Jan '98 | Feb '98 | Mar '98 | Apr '98 | May '98 | Jun '98 | Jul '98 |
|---|----------------------|----------------------|----------------------|----------------------|----------------------|----------------------|----------------------|
| Steam Generator Inspector | 529,999.36B | 481,817.60B | 529,999.36B | 529,999.36B | 643,883.52B | 722,726.40B | 755,577.60B |
| Structural Steel and Duct | 240,908.80B | 219,008.00B | 240,908.80B | 240,908.80B | 275,950.08B | 289,090.56B | 302,231.04B |
| Pressure part | 289,090.56B | 262,809.60B | 289,090.56B | 289,090.56B | 367,933.44B | 433,635.84B | 453,346.56B |
| Structural Steel and Duct | | | | | | | |
| Pressure part | | | | | | | |
| Mechanical Machine Inspector | 377,541.12B | 343,219.20B | 519,119.04B | 519,119.04B | 658,551.84B | 1,227,008.64B | 1,578,808.32B |
| Turbine Plant | 377,541.12B | 343,219.20B | 519,119.04B | 519,119.04B | 315,332.64B | 660,696.96B | 838,741.92B |
| Cooling Tower | | | | | 128,707.20B | 188,770.56B | 296,026.56B |
| Water treatment plant | | | | | 214,512.00B | 377,541.12B | 444,039.84B |
| Turbine Plant | | | | | | | |
| Cooling Tower | | | | | | | |
| Water treatment plant | | | | | | | |
| Piping Inspector | | | 238,436.00B | 238,436.00B | 357,654.00B | 953,744.00B | 1,096,805.60B |
| Steam Generator Plant and Turbine Plant | | | | | 130,056.00B | 572,246.40B | 648,112.40B |
| Cooling Tower and Water Treatment Plant | | | 238,436.00B | 238,436.00B | 227,598.00B | 381,497.60B | 448,693.20B |
| Steam Generator Plant and Turbine Plant | | | | | | | |
| Cooling Tower and Water Treatment Plant | | | | | | | |
| MEQI Inspector | 116,222.08B | 178,803.20B | 442,537.92B | 590,050.56B | 563,230.08B | 934,246.72B | 1,079,524.32B |
| NDT for Plants | | | 147,512.64B | 196,683.52B | 187,743.36B | 344,196.16B | 411,247.36B |
| Tank | 116,222.08B | 178,803.20B | 295,025.28B | 393,367.04B | 375,486.72B | 590,050.56B | 668,276.96B |
| NDT for Plants | | | | | | | |
| Tank | | | | | | | |
| Total | 1,023,762.56B | 1,003,840.00B | 1,730,092.32B | 1,877,604.96B | 2,223,319.44B | 3,837,725.76B | 4,510,715.84B |

Table 4.5: Cost of the proposed model

| | Aug '98 | Sep '98 | Oct '98 | Nov '98 | Dec '98 | Jan '99 | Feb '99 |
|---|----------------------|----------------------|----------------------|----------------------|----------------------|----------------------|----------------------|
| Steam Generator Inspector | 781,858.56B | 819,089.92B | 819,089.92B | 919,833.60B | 1,007,436.80B | 919,833.60B | 876,032.00B |
| Structural Steel and Duct | 321,941.76B | 337,272.32B | 337,272.32B | 413,925.12B | 453,346.56B | 413,925.12B | 394,214.40B |
| Pressure part | 459,916.80B | 481,817.60B | 481,817.60B | 505,908.48B | 554,090.24B | 505,908.48B | 481,817.60B |
| Structural Steel and Duct | | | | | | | |
| Pressure part | | | | | | | |
| Mechanical Machine Inspector | 1,666,758.24B | 1,840,512.96B | 1,934,898.24B | 1,982,090.88B | 2,269,536.96B | 2,072,185.92B | 2,059,315.20B |
| Turbine Plant | 855,902.88B | 943,852.80B | 991,045.44B | 991,045.44B | 1,134,768.48B | 1,036,092.96B | 1,029,657.60B |
| Cooling Tower | 360,380.16B | 377,541.12B | 377,541.12B | 360,380.16B | 444,039.84B | 405,427.68B | 386,121.60B |
| Water treatment plant | 450,475.20B | 519,119.04B | 566,311.68B | 630,665.28B | 690,728.64B | 630,665.28B | 643,536.00B |
| Turbine Plant | | | | | | | |
| Cooling Tower | | | | | | | |
| Water treatment plant | | | | | | | |
| Piping Inspector | 1,137,990.00B | 1,192,180.00B | 1,335,241.60B | 1,320,068.40B | 1,545,498.80B | 1,411,107.60B | 1,343,912.00B |
| Steam Generator Plant and Turbine Plant | 637,274.40B | 667,620.80B | 762,995.20B | 773,833.20B | 897,386.40B | 819,352.80B | 780,336.00B |
| Cooling Tower and Water Treatment Plant | 500,715.60B | 524,559.20B | 572,246.40B | 546,235.20B | 648,112.40B | 591,754.80B | 563,576.00B |
| Steam Generator Plant and Turbine Plant | | | | | | | |
| Cooling Tower and Water Treatment Plant | | | | | | | |
| MEQI Inspector | 985,652.64B | 1,081,759.36B | 1,130,930.24B | 1,079,524.32B | 1,182,336.16B | 1,079,524.32B | 1,028,118.40B |
| NDT for Plants | 375,486.72B | 393,367.04B | 442,537.92B | 422,422.56B | 462,653.28B | 375,486.72B | 357,606.40B |
| Tank | 610,165.92B | 688,392.32B | 688,392.32B | 657,101.76B | 719,682.88B | 704,037.60B | 670,512.00B |
| NDT for Plants | | | | | | | |
| Tank | | | | | | | |
| Total | 4,572,259.44B | 4,933,542.24B | 5,220,160.00B | 5,301,517.20B | 6,004,808.72B | 5,482,651.44B | 5,307,377.60B |

Table 4.5: Cost of the proposed model

| | Mar '99 | Apr '99 | May '99 | Jun '99 | Jul '99 | Aug '99 |
|---|----------------------|----------------------|----------------------|----------------------|----------------------|----------------------|
| Steam Generator Inspector | 1,007,436.80B | 963,635.20B | 919,833.60B | 963,635.20B | 963,635.20B | 1,051,238.40B |
| Structural Steel and Duct | 453,346.56B | 433,635.84B | 413,925.12B | 433,635.84B | 433,635.84B | 433,635.84B |
| Pressure part | 554,090.24B | 529,999.36B | 505,908.48B | 529,999.36B | 529,999.36B | 529,999.36B |
| Structural Steel and Duct | | | | | | 87,603.20B |
| Pressure part | | | | | | |
| Mechanical Machine Inspector | 2,368,212.48B | 2,123,668.80B | 2,027,138.40B | 2,123,668.80B | 2,123,668.80B | 2,020,703.04B |
| Turbine Plant | 1,184,106.24B | 1,085,430.72B | 1,036,092.96B | 1,085,430.72B | 1,085,430.72B | 1,038,238.08B |
| Cooling Tower | 444,039.84B | 377,541.12B | 360,380.16B | 377,541.12B | 377,541.12B | 330,348.48B |
| Water treatment plant | 740,066.40B | 660,696.96B | 630,665.28B | 660,696.96B | 660,696.96B | 566,311.68B |
| Turbine Plant | | | | | | 85,804.80B |
| Cooling Tower | | | | | | |
| Water treatment plant | | | | | | |
| Piping Inspector | 1,545,498.80B | 1,478,303.20B | 1,411,107.60B | 1,478,303.20B | 1,478,303.20B | 1,478,303.20B |
| Steam Generator Plant and Turbine Plant | 897,386.40B | 858,369.60B | 819,352.80B | 858,369.60B | 858,369.60B | 858,369.60B |
| Cooling Tower and Water Treatment Plant | 648,112.40B | 619,933.60B | 591,754.80B | 619,933.60B | 619,933.60B | 619,933.60B |
| Steam Generator Plant and Turbine Plant | | | | | | |
| Cooling Tower and Water Treatment Plant | | | | | | |
| MEQI Inspector | 1,182,336.16B | 1,130,930.24B | 985,652.64B | 1,032,588.48B | 1,032,588.48B | 1,032,588.48B |
| NDT for Plants | 411,247.36B | 393,367.04B | 281,615.04B | 295,025.28B | 344,196.16B | 344,196.16B |
| Tank | 771,088.80B | 737,563.20B | 704,037.60B | 737,563.20B | 688,392.32B | 688,392.32B |
| NDT for Plants | | | | | | |
| Tank | | | | | | |
| Total | 6,103,484.24B | 5,696,537.44B | 5,343,732.24B | 5,598,195.68B | 5,598,195.68B | 5,582,833.12B |

Table 4.5: Cost of the proposed model

| | Sep '99 | Oct '99 | Nov '99 | Dec '99 | Jan '00 | Feb '00 |
|---|----------------------|----------------------|----------------------|----------------------|----------------------|----------------------|
| Steam Generator Inspector | 1,059,998.72B | 1,011,816.96B | 1,156,362.24B | 1,208,924.16B | 1,311,857.92B | 1,333,758.72B |
| Structural Steel and Duct | 433,635.84B | 413,925.12B | 433,635.84B | 453,346.56B | 413,925.12B | 413,925.12B |
| Pressure part | 529,999.36B | 505,908.48B | 529,999.36B | 554,090.24B | 505,908.48B | 505,908.48B |
| Structural Steel and Duct | 96,363.52B | 91,983.36B | 192,727.04B | 201,487.36B | 183,966.72B | 183,966.72B |
| Pressure part | | | | | 208,057.60B | 229,958.40B |
| Mechanical Machine Inspector | 2,265,246.72B | 2,162,280.96B | 2,265,246.72B | 2,220,199.20B | 1,666,758.24B | 1,486,568.16B |
| Turbine Plant | 1,038,238.08B | 991,045.44B | 1,038,238.08B | 1,036,092.96B | 720,760.32B | 630,665.28B |
| Cooling Tower | 330,348.48B | 315,332.64B | 330,348.48B | 296,026.56B | 270,285.12B | 225,237.60B |
| Water treatment plant | 566,311.68B | 540,570.24B | 566,311.68B | 542,715.36B | 360,380.16B | 315,332.64B |
| Turbine Plant | 330,348.48B | 315,332.64B | 330,348.48B | 345,364.32B | 315,332.64B | 315,332.64B |
| Cooling Tower | | | | | | |
| Water treatment plant | | | | | | |
| Piping Inspector | 1,478,303.20B | 1,411,107.60B | 1,478,303.20B | 1,545,498.80B | 1,365,588.00B | 1,320,068.40B |
| Steam Generator Plant and Turbine Plant | 858,369.60B | 819,352.80B | 858,369.60B | 897,386.40B | 819,352.80B | 773,833.20B |
| Cooling Tower and Water Treatment Plant | 619,933.60B | 591,754.80B | 619,933.60B | 648,112.40B | 546,235.20B | 546,235.20B |
| Steam Generator Plant and Turbine Plant | | | | | | |
| Cooling Tower and Water Treatment Plant | | | | | | |
| MEQI Inspector | 907,426.24B | 985,652.64B | 1,032,588.48B | 1,028,118.40B | 750,973.44B | 657,101.76B |
| NDT for Plants | 219,033.92B | | | | | |
| Tank | 688,392.32B | 985,652.64B | 1,032,588.48B | 1,028,118.40B | 657,101.76B | 516,294.24B |
| NDT for Plants | | | | | | |
| Tank | | | | | 93,871.68B | 140,807.52B |
| Total | 5,710,974.88B | 5,570,858.16B | 5,932,500.64B | 6,002,740.56B | 5,095,177.60B | 4,797,497.04B |

Table 4.5: Cost of the proposed model

| | Mar '00 | Apr '00 | May '00 | Jun '00 | Jul '00 | Aug '00 |
|---|----------------------|----------------------|----------------------|----------------------|----------------------|----------------------|
| Steam Generator Inspector | 1,158,552.32B | 963,635.20B | 856,321.28B | 770,908.16B | 689,875.20B | 713,966.08B |
| Structural Steel and Duct | 302,231.04B | 219,008.00B | | | | |
| Pressure part | 402,974.72B | 350,412.80B | 302,231.04B | 192,727.04B | 137,975.04B | 8,760.32B |
| Structural Steel and Duct | 201,487.36B | 175,206.40B | 251,859.20B | 240,908.80B | 229,958.40B | 302,231.04B |
| Pressure part | 251,859.20B | 219,008.00B | 302,231.04B | 337,272.32B | 321,941.76B | 402,974.72B |
| Mechanical Machine Inspector | 1,628,146.08B | 1,201,267.20B | 1,377,167.04B | 1,510,164.48B | 1,370,731.68B | 1,677,483.84B |
| Turbine Plant | 690,728.64B | 514,828.80B | 542,715.36B | 424,733.76B | 64,353.60B | |
| Cooling Tower | 197,351.04B | 85,804.80B | 2,145.12B | | | |
| Water treatment plant | 345,364.32B | 171,609.60B | 141,577.92B | | | |
| Turbine Plant | 394,702.08B | 429,024.00B | 296,026.56B | 424,733.76B | 540,570.24B | 690,728.64B |
| Cooling Tower | | | 197,351.04B | 283,155.84B | 360,380.16B | 444,039.84B |
| Water treatment plant | | | 197,351.04B | 377,541.12B | 405,427.68B | 542,715.36B |
| Piping Inspector | 1,586,683.20B | 997,096.00B | 1,155,330.80B | 1,109,811.20B | 819,352.80B | 1,096,805.60B |
| Steam Generator Plant and Turbine Plant | 847,531.60B | 476,872.00B | 448,693.20B | 346,816.00B | | |
| Cooling Tower and Water Treatment Plant | 548,402.80B | 346,816.00B | 348,983.60B | | | |
| Steam Generator Plant and Turbine Plant | | | 108,380.00B | 429,184.80B | 455,196.00B | 598,257.60B |
| Cooling Tower and Water Treatment Plant | 190,748.80B | 173,408.00B | 249,274.00B | 333,810.40B | 364,156.80B | 498,548.00B |
| MEQI Inspector | 967,772.32B | 894,016.00B | 771,088.80B | 876,135.68B | 844,845.12B | 925,306.56B |
| NDT for Plants | | | | | | |
| Tank | 565,465.12B | 402,307.20B | 205,623.68B | 89,401.60B | | |
| NDT for Plants | 196,683.52B | 268,204.80B | 308,435.52B | 442,537.92B | 469,358.40B | 514,059.20B |
| Tank | 205,623.68B | 223,504.00B | 257,029.60B | 344,196.16B | 375,486.72B | 411,247.36B |
| Total | 5,341,153.92B | 4,056,014.40B | 4,159,907.92B | 4,267,019.52B | 3,724,804.80B | 4,413,562.08B |

Table 4.5: Cost of the proposed model

| | Sep '00 | Oct '00 | Nov '00 | Dec '00 | Jan '01 | Feb '01 | Mar '01 |
|---|----------------------|----------------------|----------------------|----------------------|----------------------|----------------------|----------------------|
| Steam Generator Inspector | 643,883.52B | 674,544.64B | 819,089.92B | 781,858.56B | 856,321.28B | 744,627.20B | 867,271.68B |
| Structural Steel and Duct | | | | | | | |
| Pressure part | | | | | | | |
| Structural Steel and Duct | 275,950.08B | 289,090.56B | 337,272.32B | 321,941.76B | 352,602.88B | 306,611.20B | 337,272.32B |
| Pressure part | 367,933.44B | 385,454.08B | 481,817.60B | 459,916.80B | 503,718.40B | 438,016.00B | 529,999.36B |
| Mechanical Machine Inspector | 1,621,710.72B | 1,793,320.32B | 1,840,512.96B | 1,846,948.32B | 2,022,848.16B | 1,844,803.20B | 1,982,090.88B |
| Turbine Plant | | | | | | | |
| Cooling Tower | | | | | | | |
| Water treatment plant | | | | | | | |
| Turbine Plant | 675,712.80B | 755,082.24B | 755,082.24B | 765,807.84B | 838,741.92B | 772,243.20B | 849,467.52B |
| Cooling Tower | 405,427.68B | 471,926.40B | 519,119.04B | 495,522.72B | 542,715.36B | 471,926.40B | 471,926.40B |
| Water treatment plant | 540,570.24B | 566,311.68B | 566,311.68B | 585,617.76B | 641,390.88B | 600,633.60B | 660,696.96B |
| Piping Inspector | 1,001,431.20B | 1,192,180.00B | 1,239,867.20B | 1,274,548.80B | 1,395,934.40B | 1,213,856.00B | 1,335,241.60B |
| Steam Generator Plant and Turbine Plant | | | | | | | |
| Cooling Tower and Water Treatment Plant | | | | | | | |
| Steam Generator Plant and Turbine Plant | 546,235.20B | 667,620.80B | 667,620.80B | 682,794.00B | 747,822.00B | 650,280.00B | 715,308.00B |
| Cooling Tower and Water Treatment Plant | 455,196.00B | 524,559.20B | 572,246.40B | 591,754.80B | 648,112.40B | 563,576.00B | 619,933.60B |
| MEQI Inspector | 891,780.96B | 983,417.60B | 983,417.60B | 938,716.80B | 1,028,118.40B | 894,016.00B | 983,417.60B |
| NDT for Plants | | | | | | | |
| Tank | | | | | | | |
| NDT for Plants | 516,294.24B | 590,050.56B | 590,050.56B | 563,230.08B | 616,871.04B | 536,409.60B | 590,050.56B |
| Tank | 375,486.72B | 393,367.04B | 393,367.04B | 375,486.72B | 411,247.36B | 357,606.40B | 393,367.04B |
| Total | 4,158,806.40B | 4,643,462.56B | 4,882,887.68B | 4,842,072.48B | 5,303,222.24B | 4,697,302.40B | 5,168,021.76B |

Table 4.5: Cost of the proposed model

| | Apr '01 | May '01 | Jun '01 | Jul '01 | Aug '01 | Sep '01 |
|---|----------------------|----------------------|----------------------|----------------------|----------------------|----------------------|
| Steam Generator Inspector | 827,850.24B | 856,321.28B | 781,858.56B | 819,089.92B | 856,321.28B | 744,627.20B |
| Structural Steel and Duct | | | | | | |
| Pressure part | | | | | | |
| Structural Steel and Duct | 321,941.76B | 352,602.88B | 321,941.76B | 337,272.32B | 352,602.88B | 306,611.20B |
| Pressure part | 505,908.48B | 503,718.40B | 459,916.80B | 481,817.60B | 503,718.40B | 438,016.00B |
| Mechanical Machine Inspector | 1,801,900.80B | 1,973,510.40B | 1,801,900.80B | 1,887,705.60B | 1,874,834.88B | 1,630,291.20B |
| Turbine Plant | | | | | | |
| Cooling Tower | | | | | | |
| Water treatment plant | | | | | | |
| Turbine Plant | 765,807.84B | 838,741.92B | 765,807.84B | 802,274.88B | 789,404.16B | 686,438.40B |
| Cooling Tower | 450,475.20B | 493,377.60B | 450,475.20B | 471,926.40B | 444,039.84B | 386,121.60B |
| Water treatment plant | 585,617.76B | 641,390.88B | 585,617.76B | 613,504.32B | 641,390.88B | 557,731.20B |
| Piping Inspector | 1,274,548.80B | 1,395,934.40B | 1,274,548.80B | 1,335,241.60B | 1,395,934.40B | 1,213,856.00B |
| Steam Generator Plant and Turbine Plant | | | | | | |
| Cooling Tower and Water Treatment Plant | | | | | | |
| Steam Generator Plant and Turbine Plant | 682,794.00B | 747,822.00B | 682,794.00B | 715,308.00B | 747,822.00B | 650,280.00B |
| Cooling Tower and Water Treatment Plant | 591,754.80B | 648,112.40B | 591,754.80B | 619,933.60B | 648,112.40B | 563,576.00B |
| MEQI Inspector | 938,716.80B | 925,306.56B | 844,845.12B | 885,075.84B | 925,306.56B | 804,614.40B |
| NDT for Plants | | | | | | |
| Tank | | | | | | |
| NDT for Plants | 563,230.08B | 565,465.12B | 516,294.24B | 540,879.68B | 565,465.12B | 491,708.80B |
| Tank | 375,486.72B | 359,841.44B | 328,550.88B | 344,196.16B | 359,841.44B | 312,905.60B |
| Total | 4,843,016.64B | 5,151,072.64B | 4,703,153.28B | 4,927,112.96B | 5,052,397.12B | 4,393,388.80B |

Table 4.5: Cost of the proposed model

| | Oct '01 | Nov '01 | Dec '01 | Jan '02 | Feb '02 | Mar '02 | Apr '02 |
|---|----------------------|----------------------|----------------------|----------------------|----------------------|----------------------|----------------------|
| Steam Generator Inspector | 856,321.28B | 819,089.92B | 781,858.56B | 856,321.28B | 744,627.20B | 597,891.84B | 529,999.36B |
| Structural Steel and Duct | | | | | | | |
| Pressure part | | | | | | | |
| Structural Steel and Duct | 352,602.88B | 337,272.32B | 321,941.76B | 352,602.88B | 306,611.20B | 229,958.40B | 240,908.80B |
| Pressure part | 503,718.40B | 481,817.60B | 459,916.80B | 503,718.40B | 438,016.00B | 367,933.44B | 289,090.56B |
| Mechanical Machine Inspector | 1,874,834.88B | 1,793,320.32B | 1,531,615.68B | 1,332,119.52B | 943,852.80B | 900,950.40B | 722,905.44B |
| Turbine Plant | | | | | | | |
| Cooling Tower | | | | | | | |
| Water treatment plant | | | | | | | |
| Turbine Plant | 789,404.16B | 755,082.24B | 630,665.28B | 690,728.64B | 514,828.80B | 495,522.72B | 424,733.76B |
| Cooling Tower | 444,039.84B | 424,733.76B | 360,380.16B | 345,364.32B | 171,609.60B | 135,142.56B | 15,015.84B |
| Water treatment plant | 641,390.88B | 613,504.32B | 540,570.24B | 296,026.56B | 257,414.40B | 270,285.12B | 283,155.84B |
| Piping Inspector | 1,395,934.40B | 1,335,241.60B | 1,274,548.80B | 1,346,079.60B | 1,127,152.00B | 1,092,470.40B | 762,995.20B |
| Steam Generator Plant and Turbine Plant | | | | | | | |
| Cooling Tower and Water Treatment Plant | | | | | | | |
| Steam Generator Plant and Turbine Plant | 747,822.00B | 715,308.00B | 682,794.00B | 747,822.00B | 606,928.00B | 637,274.40B | 476,872.00B |
| Cooling Tower and Water Treatment Plant | 648,112.40B | 619,933.60B | 591,754.80B | 598,257.60B | 520,224.00B | 455,196.00B | 286,123.20B |
| MEQI Inspector | 925,306.56B | 885,075.84B | 750,973.44B | 822,494.72B | 536,409.60B | 469,358.40B | 491,708.80B |
| NDT for Plants | | | | | | | |
| Tank | | | | | | | |
| NDT for Plants | 565,465.12B | 540,879.68B | 469,358.40B | 514,059.20B | 312,905.60B | 328,550.88B | 344,196.16B |
| Tank | 359,841.44B | 344,196.16B | 281,615.04B | 308,435.52B | 223,504.00B | 140,807.52B | 147,512.64B |
| Total | 5,052,397.12B | 4,832,727.68B | 4,338,996.48B | 4,357,015.12B | 3,352,041.60B | 3,060,671.04B | 2,507,608.80B |

Table 4.5: Cost of the proposed model

| | May '02 | Jun '02 | Jul '02 | Aug '02 | Sep '02 | Total |
|---|----------------------|--------------------|--------------------|--------------------|-------------------|------------------------|
| Steam Generator Inspector | 374,503.68B | 219,008.00B | 251,859.20B | 192,727.04B | 37,225.88B | 45,989,484.44B |
| Structural Steel and Duct | | | | | | 11,064,284.16B |
| Pressure part | | | | | | 13,677,049.60B |
| Structural Steel and Duct | 122,644.48B | | | | | 8,918,005.76B |
| Pressure part | 251,859.20B | 219,008.00B | 251,859.20B | 192,727.04B | 37,225.88B | 12,330,144.92B |
| Mechanical Machine Inspector | 572,733.63B | 128,707.20B | | | | 88,029,276.03B |
| Turbine Plant | | | | | | 26,402,136.96B |
| Cooling Tower | | | | | | 7,645,207.68B |
| Water treatment plant | | | | | | 12,636,901.92B |
| Turbine Plant | 444,039.84B | 128,707.20B | | | | 19,747,974.72B |
| Cooling Tower | | | | | | 9,256,192.80B |
| Water treatment plant | 128,693.79B | | | | | 12,340,861.95B |
| Piping Inspector | 611,263.20B | 346,816.00B | 49,854.80B | 43,346.58B | | 62,333,667.78B |
| Steam Generator Plant and Turbine Plant | | | | | | 18,986,008.40B |
| Cooling Tower and Water Treatment Plant | | | | | | 14,017,869.20B |
| Steam Generator Plant and Turbine Plant | 448,693.20B | 346,816.00B | 49,854.80B | 43,346.58B | | 15,999,050.18B |
| Cooling Tower and Water Treatment Plant | 162,570.00B | | | | | 13,330,740.00B |
| MEQI Inspector | 308,435.52B | 122,927.20B | 22,350.40B | | | 45,871,960.96B |
| NDT for Plants | | | | | | 6,405,624.64B |
| Tank | | | | | | 17,853,499.52B |
| NDT for Plants | 205,623.68B | 89,401.60B | 22,350.40B | | | 12,838,069.76B |
| Tank | 102,811.84B | 33,525.60B | | | | 8,774,767.04B |
| Total | 1,866,936.03B | 817,458.40B | 324,064.40B | 236,073.62B | 37,225.88B | 242,224,389.22B |

4.4 Comparison and discussion between the existing and the proposed models

The number of the resource usage of the existing and the proposed model are the same but their allocations and utilizations are different. The resource demand of the existing model depends on CMPD whereas the demand of the proposed model depends on CMD and CMPDs. However, the resource demands in unit of both models are the same. For the existing model, the resource is allocated between MD and the projects and finally from the projects back to MD. As for the proposed model, the resource is allocated among MD and the projects, and internal of the projects by following with the plan. The monitoring and adjustment of the proposed model's allocation can help to fulfill the demand of the resource all the time. There is the resource problems occur of the existing model whereas the problems will less occur in the proposed model. The resource allocation in terms of demand, supply, plan and allocation of the existing model is controlled by CMPD using manual but the allocation of the proposed model is controlled by CMPD using Microsoft Project programme. The proposed model, thus, enables the MD to allocate the resource at each time and with a lower cost and number than the existing model. Therefore, this provides MD with human resource utilization efficiently and there are remaining resources available from the proposed model for other projects of MD. Table 4.6 shows the comparison of details of the resource allocation between the allocations according to the existing model and the proposed model. It indicates that the allocation following the proposed model helps MD to allocate the resource more efficiently and allows exceed resource for other projects.

Table 4.6: Comparison of both models

| | Existing Model | Proposed Model |
|------------------------------|-----------------------------------|-----------------------------------|
| Allocation management | Depends on CMPD | Depends on CMD |
| Allocation plan | Not concerned on resource demand | Concerned on resource demand |
| Resource allocation | Between MD and the projects | Among MD and the projects |
| Monitoring | No | Controlled by CMD |
| Tool | Manual | Software |
| Utilisation | Less remaining resource available | More remaining resource available |
| Nuber of resource | More or less than demand | Conforms to demand |
| Cost | Higher | Lower |
| Allocation problem | Hihger | Lower |

4.5 Result comparison of the existing model and the proposed model

The results of the implementation of the existing and the proposed models for the projects concerning the human resource and cost are described below.

4.5.1 The existing model

For the existing model, there are resource problems: the over supply of resource and the resource shortage. The over supply of resource occurred on Project 1 because the resource was not reduced when jobs had been finished and the resource is locked to help with other jobs in the same project. As a consequence, this caused the resource shortage in Project 2. The problem lessens when the resource is reduced from Project 1. Besides, the over resource unit and the extra cost from the old model are different and higher than that of the proposed model, respectively.

4.5.2 The proposed model

For the proposed model, there are less resource problems according to the allocation. Moreover, there is remaining resource utilization which can be used for other projects. The comparison in terms of the resource utilization and extra cost of both models is described below.

- **The resource utilization**

The resource utilization is different even though they are under the same environment as mentioned in the resource usage consideration. Project 1 considered under the existing model and the proposed model will have the resource in the same demand in unit at time. The resource allocation causes the over resource in Project 1 and the resource shortage in Project 2 according to the existing model. Consequently, the resource allocation makes the resource is nearly the same amount of its demand at time of Project 1 and 2 regarding to the proposed model. Moreover, there is resource remaining. The proposed model helps MD allocate the resource closely its demand of Project 1 and 2 at time. Comparison of the resource allocation is shown in Figure 3.5. It indicates that the proposed model is better

than the existing model in helping the projects to allocate the resource to fulfill the demand at each time.




Figure 3.5: Resource utilization

- **The extra cost**

The costs of resource consist of salary, electricity allowance, providence allowance, position allowance, fringe benefit, overtime cost and traveling cost. Extra cost which is an expenditure causes from the over resource and the resource shortage was occurred only in the existing model. This means that the extra cost will be reduced by implementing the proposed model. Figure 3.6 shows the extra costs. This indicates that the proposed model can help MD save the cost.

As the results, the extra cost of the proposed model is smaller than the cost of the exiting model which are 242,224,389.22 Baht and 253,834,242.28 Baht, respectively. The cost of the existing model is higher in that of the proposed model. The proposed model can help MD save the cost as much as 11,609,853.06 Baht. It indicates that the proposed model help MD to save the extra cost.




Figure 3.6: Cost of the resource

4.6 Results of the development

The purpose of the proposed model is to help MD develop its resource allocation plan. The development can be clarified by focusing on the resource allocation and its demand, and the extra cost.

The over supply of resource and resource shortage problems in the existing model have occurred more than that of implementing of the proposed model. Moreover, there is remaining resource in proposed model.

The benefit of this research is for MD to be able to use a model for human resource allocation planning in the future multi projects. It is expected to help MD allocate its human resource for future multi projects to fulfill their demand all the times by implementing the proposed model. Moreover, the proposed model can also help MD save the extra cost from the over and shortage resource problems.

4.7 Allocation plan for the future multi projects

It has been shown in the study that the proposed model can help fulfill the resource demand with lower cost. Therefore, the model will be adapted to create an allocation plan in the future projects of MD. In general, the responsibility and scope of work of MD for the future projects to the past projects in terms of job activities and inspection procedures. The process in the plan consists of the normal practice, which has been used for management in MD, and new practice for MD.

The allocation plan

The allocation plan for the future projects will be clarified into six steps: Work Scheduling, Resource Assignment, Allocation Plan, MD to Project 1 and 2, Monitoring, Internal Allocation and Adjustment. Flow chart of the plan is presented in the following figure.




Figure 3.7: Allocation steps for MD

STEP 1: Initial project

Initial project is the first process which means the mechanical work of MD will be started. The human resource also will have started to be allocated and work conforms to the mechanical work schedule.

STEP 2: Work Scheduling

Work scheduling means the mechanical work schedule is reviewed and assigned the resource usage. The schedule consists of job activity, job duration and milestone. The schedule has already made by Engineering Division and then approved by Head of Thermal Power Plant Construction Division (TCD). The schedule is informed from TCD to CMD and then from CMD to CMPD.

After receiving the schedule, CMD reviews the schedule by checking and comparing the job activity, duration and milestone, and resource usage for each activity to the old database of MD. The database is which indicates the information of MD such as job activity, in terms of duration, milestone, its priority and their linkage, resource usage and allocation, time and cost of MD's project and so on, is recorded in a paper report. The reviewed schedule will be a final schedule for construction. Next, resource usage which is demand of the resource in position and unit at each time is considered by CMPD. And the resource demand is specified for the job activity at that time referring to the final schedule by CMPD. Finally, CMPD informs the demand data consisting of position and unit to CMD by a memorandum. This step is the normal practice of MD.

STEP 3: Resource Assignment

CMD combines the resource demand consists of position and unit of both projects and looks for the demand at each time. Next, the demand is converted into working hour and put into Microsoft project programme at resource usage view. CMD compares the demand from the programme with human resource availability of MD and then makes a decision to assign the human resource in position and unit for the demand. The assigned resource in position and unit is informed to CMPD using a memorandum by CMD. This step is a new practice for MD because at present, the resource is assigned by CMPD.

STEP 4: Allocation Plan

CMD makes the allocation plan regarding to the information in STEP 2. The allocation consists of four types of the allocation: MD to Project 1 and 2, Internal Allocation,

Project 1 and 2 and Project 1 and 2 to MD. The information in this step is sent to CMD by a memorandum. CMD will make a final decision for the allocation because CMPD has higher authority than CMPD in organization. This step is the new process because the plan is made by CMPD in practice.

STEP 5: Allocation

The resource is allocated following to the plan in STEP 3. CMD makes official letter for the allocation. This process is the old practice in MD because of all official letters in MD are made under responsibility of CMD. Lag time of the resource allocation is a duration time for the resource allocated from one to the other project and from MD to the project when the demand changed occurs. The allocation is begin with the changed demand in STEP 6 is informed to CMD by CMPD. Then CMD checks the resource availability and the changed demand at that time. The resource availability and demand, which is the peak unit, are indicated in resource usage view in Microsoft Project Programme. Different of the resource availability and demand in working hour will be converted into unit by divided with working hour per day. The different resource in unit shows the remaining resource in the project. Also the availability resource in MD will be checked. The remaining resources are considered to allocate referring to the workload demand in the project. Next, CMD makes official letter to CMD and to the remaining resource to allocate to the project where is required the resource. Finally, the resource is allocated. The checking time and allocation time spend one day of each. The total duration which is the checking time and the allocation time is two days. Therefore, the lag time of the allocation is two days. It means the resource will be allocated from one to the other project or MD within two days. According to an interviewing to the person who were been CMPD of the past projects, the resource was allocated from one to other project taking approximately two weeks. That is the old practice of MD. Therefore, the main reasons for CMD to allocate the resource within the lag time are CMD's authorize and Microsoft Project programme. In practice, CMD is the top management of MD so that all managements are run under responsibility of CMD. Therefore, CMD can easily manage the allocation by following the plan. Moreover, Microsoft Project programme is useful for CMD to collect data and look for the resource demand and requirement of the allocation. Due to the reasons, the resource can be allocated within the lag time.

STEP 6: Monitoring

The purpose of this step is to follow up the resource allocation and compare the resource workload with its demand at each time. This process is controlled by CMD. The monitoring consists of three items: Follow up. Comparing and Summarize (see Figure 3.8).




Figure 3.8: Monitoring process for MD

1. Follow up

This process is to follow up the allocation according to the plan in terms of resource unit and its position. The follow up can be divided into 2 types: Monthly and Other cases. CMD will consider selecting one of the types after allocation. Details of the follow up are described as follow.

1.1. Monthly

This process is an action once a month. In practice, there has a monthly meeting and report between CMD and CMPDs at the beginning of each month. Therefore, the meeting and report should be done to follow up the allocation. The meeting and report are presented as follow.

1.1.1. Meeting

The meeting is to look for the progress of work and the workload. The meeting between MD and CMPD or their representatives are set at site or MD in monthly at the beginning of the month in order to get the information of the project. The information consists of data in the project focusing on the work in progress and the resource in position and unit. The meeting has to be mentioned about the data of the previous, present and next month. After the meeting the report is made by CMPD and submitted to CMD. The meeting should be on between the first to the fifth of each month.

1.1.2. Report

CMD assigns CMPD to submit report of information of resource allocation and its workload information of the project after the meeting. The information consists of the mechanical work in progress and the resource workload in position and unit. The work and workload are clarified in Monthly Progress Report (see Appendix C). The schedule presents the job activity, duration and milestone, linkage and the resource workload in the previous, present and next month in the project. The previous, present and next month shows the month information in a month before, present month and next month, respectively. The report shows the work progress compared to the work schedule in that month. If the schedule is changed, it will cause the resource demand changed. Such changed schedule and changed demand are also identified in the information by CMPD. In the last, information consists of the position and unit, and the work progress from this process are submitted from CMPD to CMD.

1.2. Other cases

The other cases mean that the changed demand occurs between the beginning and the end of each month. The resource demand in position and unit are informed from CMPD to CMD by using a memorandum which is described as below.

Memorandum

In case demand changed in which the resource should be increased or decreased from the project within month, CMPD has to inform CMD by a memorandum. The memorandum is made to inform CMD of the required resource at first by calling, fax, and email and then officially submitted. In case the demand is changed, STEP 5 and STEP 6 will be considered. This process is similar to the old practice because a memorandum is used to communicate in MD.

2. Comparing

CMD compares the workload and demand from item 1 to that of the schedule plan and the old data of MD. Firstly, the progress work which is the actual work is compared to the work schedule to look for the remaining work. The remaining work and its demand identified by CMPD are collected by CMD as mentioned in item 1.1.2. When the changed schedule occurs, CMD revises to up date the schedule. Secondly, the demand in position and unit, and its workload are reviewed for matching to the revised schedule. CMD checks whether the unit conforms to its workload or not. The checking can be made by comparing the unit with the workload to the previous duration, in Monthly Progress report, or from one to the other project incase the work is similar. The demand is converted to be the workload in hour. Then the revised schedule and the workload are put into Microsoft Project programme at Gantt chart and resource usage view, respectively by CMD. CMD accesses whether the problems which are the over supply or the resource shortage occur or not. Therefore, the different unit for the project is made by CMPDs. This process is the new practice because there is no person who responsible for comparing the allocation to the demand in MD.

3. Summarize

The demand in position and unit in item 2 is summarized after comparing by CMD. In case the demand is changed, STEP 4 and STEP 6 will be considered. In case the resource demand is equal to the resource allocation. CMD records the information of the job and workload to be the database of MD. This process is the new practice because there is no summarize in MD.

STEP 7: Internal Allocation

When the demand changed, the schedule has to change. It is responsibility of CMPD to manage the resource allocation within his/her project. Then the allocation information is sent to CMD and also if there is still being the changed demand, CMPD should inform that demand to CMD. A detail of the information is sent from CMPD to CMD by calling, fax or email of the memorandum. Then STEP 6 will be considered. In case the resource whether be idled in the project waiting for their work, CMD should consider focusing on the cost and demand of the other project. This step is normal practice of MD.

STEP 8: Adjustment

CMD puts the changed demand specified in STEP 5 into Microsoft project programme in resource usage view and accesses the resource problems which are the resource shortage or the over supply of resource. Then the process will be backed to the allocation plan in STEP 3. This step is new practice because there is no adjustment in MD.

STEP 9: Finished project

The human resource is allocated return to MD when the work finished under management of CMD. The allocation is informed to CMPD to allocate the resource by calling, fax or email and then the official letter is made for the allocation by CMD.

4.8 Possibility of the plan implementation

According to the steps, some steps are new for MD so that the new steps were considered to prove by involved personnel who are CMD and will be a CMPD of the future multi projects before implement to the future projects. For acceptance of the concern personnel, the explanation and interview in terms of the plan and Microsoft project programme are made. The possibility of the plan implementation can be explained in terms of management and Microsoft Project Programme as follow.

4.8.1 Management

In practice, CMPD controls the resource demand and plan the allocation because he will have authorized from CMD in order to manage the allocation. However, the official of the allocation is done by CMPD because he is the top management who has the highest authority in MD. As the allocation plan allows CMD controls the allocation, it is the same direction of the management in MD that the plan is run under CMD's management. Therefore, it is possible for changing the management personnel according to the plan from CMPD to be CMD.

4.8.2 Microsoft Project programme

The record data from Personal Department shows that the involved personnel have already been trained in Microsoft project programme. In addition, Microsoft project programme has just begun to use in MD. Therefore, CMD can easily use the programme as a tool for the plan.

As the result, CMD and CMPD agree with the plan that could help the allocation more effectively. In the last, CMD and CMPD are pleased with the allocation of the resource by following the plan.